

**DRILLING PLAN
WEXPRO COMPANY
POWDER WASH GOVERNMENT NO. 5
MOFFAT COUNTY, COLORADO**

1. SURFACE FORMATION, ESTIMATED- TOPS AND WATER, OIL, GAS OR MINERAL BEARING FORMATIONS:

Wasatch	Surface
A-4-G SD	4,610' , gas - Secondary Objective
A-4-H SD	5,266' , gas - Secondary Objective
Fort Union	5,494'
Allen 8 - A	6,360'
Allen 8 - B	6,407' , gas, - Major Objective
Allen 8 - E	6,554'
Allen 8 - F	6,675' , gas, - Major Objective
Allen 8 - G	6,712'
Allen 8 - H	6,789'
Allen 9 - A	6,957' , gas, - Secondary Objective
Allen 9 - B	7,007' , gas, - Secondary Objective
Allen 9 - C	7,106'
Allen 11	7,229'
L. F. U. 4600	7,828'
Allen 10 - B	8,131'
Allen 10 - C	8,173'
Allen 6 - A	8,321'
Allen 6 - G	8,809' , gas, - Major Objective
Allen 6 - H	8,904' , gas, - Major Objective
Allen 6 - K	9,061' , gas, - Major Objective
Lance	9,235'
Total Depth	9,411'

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected.

2. **PRESSURE CONTROL EQUIPMENT:** (see attached diagram) Operator's minimum specifications for pressure control equipment require an 11-inch 3000 psi double gate hydraulically operated blowout preventer and an 11-inch 3000 psi annular preventer. BOP equipment will be tested to its rated working pressure or 70-percent of the internal yield of the surface casing. The annular preventer will be tested at 50-percent of its rated working pressure. NOTE: The surface casing will be pressure tested to a minimum of 1500 psi. BOP's will be checked daily as to mechanical operating condition and will be tested by rig equipment after each string of casing is run. All ram type preventers will

have hand wheels which will be operative and accessible at the time the preventers are installed. Accumulator will include both electric and air power source (see attached diagram).

At this time Wexpro Company requests approval, if needed, to use "Flex Hose" between the BOP and Choke Manifold. The Flex Hose will have a minimum rating of 5,000 psi. Please see the attached specifications sheet for more details.

AUXILIARY EQUIPMENT:

- a) Manually operated kelly cock
- b) No floats at bit
- c) Monitoring of mud system will be visual
- d) Full opening floor valves in the full open position, capable of fitting all drill stem connections manually operated

3. CASING PROGRAM:

Size		Top Bottom		Weight	Grade	Thread	Condition
Hole	Casing						
20"	16"	sfc	80'	Steel Pipe Conductor			New
12-1/4"	9-5/8"	sfc	1500'	36#	J55	LT&C	New
7-7/8"	4-1/2"	sfc	9,411' MD	13.5#	P-110	LT&C	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
9-5/8'	36 lb.	J55	LTC	2,020 psi	3,520 psi	453,000 lb.
4-1/2"	13.5 lb.	P110	LTC	10,670 psi	12,410 psi	338,000 lb.

Area Fracture Gradient: 0.750 psi/foot

The variance to Onshore #2 is requested because surface casing depth for this well is 1500' and high pressure is not expected.

A properly lubricated and maintained rotating head: A diverter bowl will be utilized in place of a rotating head. The diverter bowl will force the air and cutting returns to the reserve pit as it is used to drill the surface casing.

Blooi line discharge will be 100 feet from the well bore and securely anchored: The blooi line discharge for this operation will be located 50 to 70 feet from the wellhead.

Automatic ignitor or continuous pilot light on the blooi line: A diffuser will be used rather than an automatic pilot/ignitor. Water is injected into the compressed air and eliminates the need for the pilot light and the need for dust suppression equipment.

Compressor located in the direction from the blooi line is a minimum of 100' from the well bore: Truck mounted air compressors will be located within 50 feet on the opposite side of the wellhead from the blooi line and equipped with a (1) emergency kill switch on the driller's console, (2) pressure relief valve on the compressor and (3) spark arrestors on the motors.

CEMENTING PROGRAMS: (See Attached Details)

9-5/8" Surface Casing: Lead Slurry: 585 cubic feet Class "G" with 2% CaCl₂ and 1/4 % cello flake (only if lost circulation is encountered).

Tail Slurry: 395 cubic feet Class "G" with 2% CaCl₂ and 1/4 % cello flake (only if lost circulation is encountered).

4-1/2" Production Casing: Lead Slurry: 1265 cubic feet Light 50/50 Poz-G with retarder, reducer and fluid loss additive. Volume to be calculated from caliper logs to bring lead cement from 4,200' to surface, with 15% excess.

Tail Slurry: 1369 cubic feet 35/65 Poz-G with retarder, reducer and fluid loss additive. Volume to be calculated from caliper logs to bring tail cement from TD to 4,200', with 15% excess.

4. MUD PROGRAM:

- 1) Surface hole mud drilled and cased with the Drilling rig.
- 2) Surface casing will be drilled out 10 feet and formation tested to 10.0 ppg mud equivalent.
- 3) Fresh water with gel and polymer sweeps as necessary. Mud weight of 9.5 - 10.0 ppg to be accomplished by 5,000 feet to total depth, if needed.
 - A. Mud weight 9.0 - 10.0 ppg
 - B. Viscosity 35 - 45 cp
 - C. PH 10
 - D. Water Loss <7

E.	Type	Fresh water and dispersed mud
F.	Asphalt	6 lb/sack

Sufficient mud materials to maintain mud properties, control lost circulation and to contain blowout will be available at the wellsite.

No chrome constituent additives will be used in the mud system on Federal, State and Indian lands without prior BLM/State approval to ensure adequate protection of fresh water aquifers.

5. LOGGING:

DIL-SFL-GR:	Total depth to surface casing.
BHC-Sonic-GR:	Total depth to surface casing.
FDC-CNL-GR-PE-Cal:	Total depth to surface casing.
Cement/Bore Hole Profile Log	

TESTING: None.

CORING: None.

6. ABNORMAL PRESSURE AND TEMPERATURE: A BHT of 191° F and a BHP of 3500 psi are possible.

7. ANTICIPATED STARTING DATE: March 1, 2011

DURATION OF OPERATION: 25 days

Construction

Tube: Black, oil and abrasion resistant HNBR for H₂S service.

Reinforcement: Multiple plies of bias laid textile cord for extra strength and flexibility. Spirally wound, high tensile, multiple strand cables to provide unsurpassed ruggedness and reliability to withstand sudden high pressure.

Cover: Special flame resistant red Neoprene (CR) with optional stainless steel armor.

Fittings: Integral connection flanged or hubbed.

Temperature: -40°F to 212°F.


Branding: NRP Choke & Kill Hose. MADE IN USA.

Specifications

NRP Part Number	Hose ID (in)	Hose OD (in)	Rated WP (psi)	Test Pressure (psi)	Minimum Bend Radius	Weight per Foot (lbs)
5035-32	2.00	4.45	5,000	10,000	44	12.9
5035-40	2.50	4.60	5,000	10,000	48	13.9
5035-48	3.00	5.10	5,000	10,000	52	16.1
5040-32	2.00	4.68	10,000	15,000	48	22.4
5040-40	2.50	5.34	10,000	15,000	52	27.4
5040-48	3.00	5.84	10,000	15,000	56	28.8

Specifications

NRP Rotary Number	NRP Vibrator Number	Hose ID (in)	Hose OD (in)	Grade	Rated WP (psi)	Test Pressure (psi)	Minimum Bend Radius	Weight per Foot (lbs)	Weight of 2' Cplgs (lbs)	Cplg Thread API (in)
5501-40	5502-40	2.50	4.45	C	4,000	8,000	36	12.9	54	3
5501-48	5502-48	3.00	4.95	C	4,000	8,000	48	14.9	74	4
5501-56	5502-56	3.50	5.45	C	4,000	8,000	54	16.6	94	4
5603-40	5604-40	2.50	4.60	D	5,000	10,000	36	13.6	54	3
5603-48	5604-48	3.00	5.10	D	5,000	10,000	48	15.5	74	4
5603-56	5604-56	3.50	5.75	D	5,000	10,000	54	18.6	94	4



POWDER WASH GOVT. 5 : CEMENT CALCULATIONS

SURFACE CASING:

CASING:	9.625 " 36#, K-55	0.4340 cu.ft./lin.ft	ID= 8.921
ANNULUS:	12.250 " x 9.625" Gauge Hole	0.3131 cu.ft./lin.ft	
CONDUCTOR	16.000 " STEEL PIPE	0.8908	
EXCESS:		100%	
CEMENT YIELD:	LEAD	2.65 cu.ft./sack 11.5 PPG	
	TAIL	1.26 cu.ft./sack 15.2 PPG	
CONDUCTOR DEPTH		80	
TOTAL DEPTH		1,500 Feet	
TOP OF TAIL		900 Feet	
TOP OF LEAD		0 Feet (Surface)	

LEAD SLURRY						CU.FT	
COND/CSG ANN	80	TO	0	0.8908	71.27		
ANN (OH)	900	TO	80	0.3131	256.77		
ANN EXCESS				100%	256.77		
					584.80	221 SACKS	584.8 CU.FT.

TAIL SLURRY						CU.FT	
CSG SHOE (45')	1,500	TO	1,455	0.4340	19.53		
COND/CSG ANN	-	TO	-	0.8908	0.00		
ANN (OH)	1,500	TO	900	0.3131	187.88		
ANN EXCESS				100%	187.88		
					395.28	314 SACKS	395 CU.FT.
					DISPLACEMENT	112.5 BBLS	

PRODUCTION CASING:

CASING:	4.500 ", 13.5#, P-110	0.0838 cu.ft./lin.ft	ID= 3.92
ANNULUS:	7.875 "(For Gauge Hole)	0.2278 cu.ft./lin.ft	
	8.921 " ID x 4-1/2" CASING ANNULUS	0.3236 cu.ft./lin.ft	
EXCESS:		15%	
CEMENT YIELD:	LEAD	2.63 cu.ft./sack 11.5 PPG	
	TAIL	1.49 cu.ft./sack 14.2 PPG	
TOTAL DEPTH		9,411 Feet	
TOP OF TAIL		4,200 Feet	
TOP OF LEAD	OPEN HOLE TOP	1,500 Feet	
	CASED HOLE TOP	SURFACE Feet	


LEAD SLURRY						CU.FT	
ANN	4,200	TO	1,500	0.2278	614.93		7-7/8" (For Gauge hole)
	1,500	TO	0	0.3236	485.34		9-5/8" X 4-1/2" Casing Annulus
ANN EXCESS				15%	165.04		
					1265.31	481 SACKS	1265 CU.FT.

TAIL SLURRY						CU.FT	
CSG	9,411	TO	9,366	0.0838	3.77		
ANN	9,411	TO	4,200	0.2278	1186.82		
ANN EXCESS				15%	178.02		
					1368.62	919 SACKS	1369 CU.FT.
					DISPLACEMENT	139.8 BBLS	

QUESTAR WELPR

3,000 psi BOP

Minimum Requirements



3M CHOKE MANIFOLD EQUIPMENT — CONFIGURATION MAY VARY

46812

Federal Register / Vol. 53, No. 223 / Friday, November 18, 1988 / Rules and Regulations

