

WELLBORE DIAGRAM

Directions: WCR 70 at WCR 25, 0.2 mi S, 0.2 mi SE into

Bayswater Exploration & Prod Kochert 12-18

SWNW 18 6N 66W
SHL: 1953' FNL 733' FWL

Updated
2/4/2013
MMA

Weld County CO
05-123-26748

G.L.= 4846
K.B.= 4856
10

8-5/8" 24# set at 719'
Cmt'd w/ 510 sx to Surf.

CBL TOC: 3340'

<<

>>

CODELL: 7214'-7226', 4 spf, Reperf 7214'-7226, 2 spf, 24 shots.
Original frac 9/3/08, slickwater w/ 87,332# 30/50 sand
Refrac on 2/4/13, with 269,366 gals Slickwater, and 180,240 lbs. 20/40 White

PBTD= 7,319'

4 1/2", 11.6# LTC 7359' (7-7/8" O.H.)

TD MD= 7,389'

Cmt'd w/ 495 sx

TD VD= 7,389'