

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400402206

Date Received:

04/30/2013

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8268

Email: greg.j.davis@wpxenergy.com

7. Well Name: Federal Well Number: RGU 343-26-198

8. Unit Name (if appl): Ryan Gulch Unit Unit Number: COC068269

9. Proposed Total Measured Depth: 12592

WELL LOCATION INFORMATION

10. QtrQtr: LOT 8 Sec: 26 Twp: 1S Rng: 98W Meridian: 6

Latitude: 39.935101 Longitude: -108.354578

Footage at Surface: 2460 feet FNL/FSL 905 feet FEL/FWL FEL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6623 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 02/14/2013 PDOP Reading: 2.0 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2125 FSL 632 FEL FEL Bottom Hole: FNL/FSL 2125 FSL 632 FEL FEL
Sec: 26 Twp: 1S Rng: 98W Sec: 26 Twp: 1S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 263 ft

18. Distance to nearest property line: 6912 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 328 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Sego	SEGO			
Williams Fork	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC60732

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

☒

23. Is the Surface Owner also the Mineral Owner? Yes ☐ No ☐ Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T1S R98W: Sec 23: Lots 1-16; Sec 26: Lots 2-16

25. Distance to Nearest Mineral Lease Line: 632 ft 26. Total Acres in Lease: 1206

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	18	48	0	80	50	80	0
SURF	14+3/4	9+5/8	36	0	3,875	1,404	3,875	0
1ST	8+3/4	4+1/2	11.6	0	12,592	1,295	12,592	7,522

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of cement for production casing will be at least 200 feet above the top of Mesaverde. Closed mud system will be used. Federal minerals and surface. The wells will be drilled from the newly constructed RGU 42-26-198 well pad. See WPX energy Master APD Dated 4/27/06 for Federal 10 Point Drilling Plan.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 4/30/2013 Email: howard.harris@wpxenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 6/13/2013

API NUMBER

05 103 11967 00

Permit Number: _____ Expiration Date: 6/12/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

Applicable Policies and Notices to Operators

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400402206	FORM 2 SUBMITTED
400411670	FED. DRILLING PERMIT
400411671	LEGAL/LEASE DESCRIPTION
400411672	WELL LOCATION PLAT
400411673	DIRECTIONAL DATA
400411674	DEVIATED DRILLING PLAN
400411675	DEVIATED DRILLING PLAN

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed contact info per oper. No LGD or public comments. Final Review--passed.	6/11/2013 11:31:04 AM
Permit	Corrected qtr/qtr. Distance to nearest unit boundary is greater than one mile.	5/30/2013 7:37:14 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 3001 FEET DEEP.	5/6/2013 9:25:50 AM
Permit	Passed completeness.	5/1/2013 10:20:18 AM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>