

# WELL LOCATION CERTIFICATE: BADGER CREEK 22-32B

SECTION 22, TOWNSHIP 2 SOUTH, RANGE 57 WEST, 6TH P.M.

NW SEC. 22  
2½" ALUM. CAP  
PLS 38231

N 88°57'52" E 5243.72'

NE SEC. 22  
¾" ALUM. CAP  
PLS 14142

NOTES:  
BH LOCATION PROVIDED BY CLIENT.  
LAND SURFACE USE- RANGELAND  
SEE ATTACHED MAP FOR ADDITIONAL  
IMPROVEMENTS WITHIN 400'.

PDOP= 4.4  
GPS OPERATOR: DAVID MACDONALD

N 01°21'00" W 5319.31'

22

BADGER CREEK  
22-32B

S 01°11'39" E 5282.54'  
(BASIS OF BEARINGS) SEE NOTE 3

SURFACE LOCATION  
GROUND ELEVATION= 4651'  
NAD83  
LATITUDE= 39.864818°  
LONGITUDE= 103.747518°

SW SEC. 22  
2½" ALUM. CAP  
PLS 38231

S 88°33'44" W 5229.28'

SE SEC. 22  
2½" ALUM. CAP  
PLS 38231

WELL BADGER CREEK 22-32B TO BE LOCATED 2227' FNL AND 1461' FEL

## LEGEND


⊕ = EXISTING MONUMENT    ⊕ = BOTTOM HOLE  
● = PROPOSED WELL        ◆ = EXISTING WELL  
BH = BOTTOM HOLE

## NOTES:

1. THIS FIELD SURVEY CONFORMS TO THE MINIMUM STANDARDS SET BY THE C.O.G.C.C., RULE NO. 215
2. HORIZONTAL POSITIONS AND ORTHOMETRIC ELEVATIONS SHOWN AT THE WELL HEAD, ARE BASED ON GPS-RTK POSITIONS DERIVED FROM MINIMUM 2-HOUR STATIC OBSERVATIONS CORRECTED BY THE NATIONAL GEODETIC SURVEY ONLINE POSITIONING USER SERVICE, O.P.U.S. DATUM: HORIZONTAL = NAD83/2011, VERTICAL = NAVD88
3. THE BASIS OF BEARINGS ARE STATE PLANE COORDINATE SYSTEM GRID BEARINGS SHOWN HEREON BETWEEN THE DESCRIBED MONUMENTS SHOWN HEREON.
4. GRID DISTANCES ARE SHOWN, AS MEASURED IN THE FIELD, WITH TIES TO WELLS MEASURED PERPENDICULAR TO SECTION LINES.

I, MARK A. HALL, A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO DO HEREBY CERTIFY TO BAYSWATER EXPLORATION & PRODUCTION, LLC, THAT THE SURVEY AND WELL LOCATION CERTIFICATE SHOWN HEREON WERE DONE BY ME OR UNDER MY DIRECT SUPERVISION AND THAT THE DRAWING SHOWN HEREON ACCURATELY DEPICTS THE PROPOSED LOCATION OF THE WELL. THIS CERTIFICATE DOES NOT REPRESENT A LAND SURVEY PLAT OR IMPROVEMENT SURVEY PLAT AS DEFINED BY C.R.S. 38-51-102 AND CANNOT BE RELIED UPON TO DETERMINE OWNERSHIP.

MARK A. HALL, PLS 36073  
COLORADO LICENSED PROFESSIONAL LAND SURVEYOR  
FOR AND ON BEHALF OF P.F.S., LLC



SCALE: 1"=1000'



PREPARED BY:



FIELD DATE:

04-25-13

DRAWING DATE:

05-07-13

BY:

KAD

CHECK:

MLP

SURFACE LOCATION:

SW 1/4 NE 1/4,

SEC. 22, T2S, R57W, 6TH P.M.

ADAMS COUNTY, COLORADO

NOTICE: ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THIS SAID DATE OF THIS CERTIFICATION SHOWN HEREON.

