

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400408846

Date Received:

06/14/2013

PluggingBond SuretyID

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Julie Webb Phone: (303)831-3933 Fax: ()

Email: julie.webb@pdce.com

7. Well Name: Alles Well Number: 22D-212

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12587

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 22 Twp: 5N Rng: 65W Meridian: 6

Latitude: 40.383340 Longitude: -104.641910

Footage at Surface: 2125 feet FNL/FSL 559 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4645 13. County: WELD

14. GPS Data:

Date of Measurement: 03/20/2013 PDOP Reading: 1.6 Instrument Operator's Name: Brian Rottinghaus

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1828 FSL 490 FEL 1830 FSL 500 FEL 1830 FSL 500 FEL 1830
Sec: 22 Twp: 5N Rng: 65W Sec: 23 Twp: 5N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 533 ft

18. Distance to nearest property line: 186 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 109 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		400	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NESE of Section 22 (5N-65W) Horizontal wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is 510'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 40

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	830	875	0
1ST	8+3/4	7	26	0	7,340	650	7,340	500
1ST LINER	6+1/8	4+1/2	11.6	6136	12,587			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 400 acres, E2SE of Sec. 22 and S2 of Sec. 33 T5N R65W. Proposed spacing unit map and 30-day certificate is attached. Distance to nearest well measured by Anti-Collision report in the Directional Survey.

34. Location ID: 327103

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Webb

Title: Regulatory Analyst Date: 6/14/2013 Email: julie.webb@pdce.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\Inetpub\NetReports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400408846	FORM 2 SUBMITTED
400425504	PLAT
400425505	DEVIATED DRILLING PLAN
400425506	DIRECTIONAL DATA
400425729	30 DAY NOTICE LETTER
400425732	EXCEPTION LOC WAIVERS
400425761	EXCEPTION LOC REQUEST
400425785	VARIANCE REQUEST
400432204	PROPOSED SPACING UNIT
400433798	OFFSET WELL EVALUATION

Total Attach: 10 Files

General Comments

User Group	Comment	Comment Date
Permit	Location should be amended. Opr notified and form back to draft.	6/17/2013 11:55:19 AM

Total: 1 comment(s)

BMP

Type	Comment
Drilling/Completion Operations	Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012. The Colorado Oil and Gas Conservation Commission (COGCC) has established this Policy Regarding Bradenhead Monitoring During Hydraulic Fracturing Treatments ("Treatment") in the Greater Wattenberg Area ("GWA") pursuant to COGCC 207.a. ("Policy"). This Policy applies to oil and gas operations in the GWA as defined by the COGCC Rules of Practice and Procedure.
Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.

Total: 2 comment(s)