

**Magna Energy Services, LLC
17509 County Rd. 14
Ft. Morgan, Co 80701
(970) 867-9007
Fax (970) 867-8374**

Job Log

Date: 5/9/2013

Operator: Enerplus Resource Corp.

Well Name: Koester 6-52-27-44

Legal Location: SESE Sec. 27-6N-52W

Location: Sterling, CO

5/2/2013: MIRU, ROH with 2 3/8 " tubing, Wireline RIH with 3.5" JCGR to 3944', Tag existing CIBP, DB 2 sxs of cement on top of existing CIBP (per Dirk Sutphin COGCC), Wireline set CIBP @ 3800'

5/3/2013: DB 2 sxs of cement on top of CIBP @ 3800', Free Point casing @ 3100', Cut casing @ 3060', ROH with 4 1/2 " casing, RIH with 2 3/8 " tubing to 2530' (Could not work tubing down hole)

5/6/2013: Mix and pump 40 sxs of cement @ 2530' (Per Jim Percup COGCC), ROH to 619', Mix and pump 60 sxs of cement, WOC, Tag TOC @ 575', Mix and pump 15 sxs of cement, ROH with 2 3/8 " tubing to 72', Mix and pump 16 sxs of cement until good returns @ surface, RD rig

5/7/2013: Dig out well head 4' below ground level, Cut off well head 4' below ground level, Weld on cap with all legal information, P&A complete Magna Energy Services, LLC

Total: 72 Joints of 4 1/2 " 10.5# casing
122 joints of 2 3/8 " tubing

****All Cement pumped was 15.8# Class "G" Neat with high yield of 1.15#****

Cementing Contactor: Magna Energy Services, LLC
Cementing Contractor Supervisor: Brandon Chappel
Operation Supervisor: Ron Parham
COGCC Representative: Kym Schure
Wireline Contractor: Magna Energy Services, LLC