

Magna Energy Services, LLC
17509 County Road 14
Ft. Morgan, CO 80701
(970) 867-9007
Fax (970) 867-8374

Job Log

Date: 5/15/2013

Operator: Enerplus Resources Corp.

Well Name: Blach 4-54-9-33

Legal: NWNE Sec. 33-7N-51W

Location: Hillrose, CO

5/10/2013

MIRU, MIRU wireline, Wireline RIH with JCGR to 4096', Wireline set CIBP @ 3975', Wireline DB 2 sxs of cement on top of CIBP, SDFN

5/13/2013

Wireline cut casing @ 3436', ROH with 73 joints of 10.5# 4 1/4" casing, RIH with 2 3/8" tubing to 3586', Mix and pump 40 sxs of cement, ROH with 2 3/8" tubing to 523', Mix and pump 60 sxs of cement, SDFN

5/14/2013

RIH with 2 3/8" tubing, Tag TOC @ 345', ROH with 2 3/8" to 65', Mix and pump 35 sxs of cement until good return @ surface, ROH with 2 3/8" tubing, Dig well head 4' below ground level, Cut off well head 4' below ground level, weld on plate with all legal information, back fill pit, P&A complete

** All cement pumped was 15.8# Class "G" Neat with a yield of 1.15# **

Cement Contractor: Magna Energy Services, LLC
Cementing Contractor Supervisor: Brandon Chappel
Operation Supervisor: Ron Parham
COGCC Representative: Kym Schure
Wireline Contractor: Magna Energy Services, LLC