



STATE OF COLORADO




Krabacher - DNR, Jay <jay.krabacher@state.co.us>

Change in P&A procedure to Windor's Fed. Mtn Fuel 5-34 (103-08124)

1 message

Krabacher - DNR, Jay <jay.krabacher@state.co.us>
To: chad vannest <chadvannest@hotmail.com>
Cc: "Browning, Chuck" <Chuck.Browning@state.co.us>



Fri, Jun 20, 2013 at 4:26 PM

Mr. Vannest:

As we discussed by phone a little while ago, in regards a COGCC Form 6 (intent to abandon the subject well) – there may be no need to place 15 (or however how many) additional sacks of cement at the surface. I said that people filling out the intent forms may sometimes arbitrarily put "10" (or 15 or so) sacks for a surface plug.

In this instance, when Magna has finished the surface-shoe cement plug and has proceeded to cutting off the casings 4' (or whatever depth specified) below surface – IF THERE ARE ANY ANNULUSES OR CASINGS which do not have cement to surface, then the Contractor should "one inch" or whatever other appropriate means, cement in any such open spaces to a depth of at least 50'. Obviously, if it is apparent that there is cement to surface in all annuluses and casing strings, there is no further need for any more cement.

Regards,

–
Jay Krabacher
N W Area Engineer
C O G C C

cosas son mas como son ahora que ellas siempre fueron