

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400422294

Date Received:

05/22/2013

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-36362-00

6. County: WELD

7. Well Name: POWERS

Well Number: 4C-27HZ

8. Location: QtrQtr: SWSW Section: 27 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 510 feet Direction: FSL Distance: 600 feet Direction: FWL

As Drilled Latitude: 40.103720 As Drilled Longitude: -104.657137

GPS Data:

Data of Measurement: 02/14/2013 PDOP Reading: 1.5 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 740 feet. Direction: FSL Dist.: 1078 feet. Direction: FWL

Sec: 27 Twp: 2N Rng: 65W

** If directional footage at Bottom Hole Dist.: 484 feet. Direction: FNL Dist.: 1052 feet. Direction: FWL

Sec: 27 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 12/15/2012 13. Date TD: 02/09/2013 14. Date Casing Set or D&A: 02/11/2013

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11810 TVD** 7239 17 Plug Back Total Depth MD 11785 TVD** 7239

18. Elevations GR 4935 KB 4941

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

GR/RES/MUD

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36.0	0	1,845	645	0	1,845	CALC
1ST	8+3/4	7	26.0	0	7,766	740	520	7,766	CBL
1ST LINER	6+1/8	4+1/2	11.6	6689	11,795				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,967		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,084		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,484		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,585		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joel Malefyt

Title: Regulatory Analyst Date: 5/22/2013 Email: joel.malefyt@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400422310	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400422308	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400422294	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422320	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422373	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422526	PDF-INDUCTION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422528	LAS-INDUCTION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422529	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400422549	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)