

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400422531

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20120105

3. Name of Operator: CARRIZO NIOBRARA LLC

4. COGCC Operator Number: 10439

5. Address: 500 DALLAS STREET #2300

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Tina Taylor Phone: (713)328-1000 Fax: (713)328-1060

Email: tina.taylor@crzo.net

7. Well Name: State Well Number: 2-36-9-61

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10792

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 36 Twp: 9N Rng: 61W Meridian: 6

Latitude: 40.711710 Longitude: -104.149490

Footage at Surface: 302 feet FNL/FSL FNL 1041 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4932 13. County: WELD

14. GPS Data:

Date of Measurement: 05/09/2013 PDOP Reading: 2.6 Instrument Operator's Name: Marc Woodard

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 600 FNL 600 FEL 600 FEL 600
Bottom Hole: FNL/FSL 600 FSL 600 FEL 600
Sec: 36 Twp: 9N Rng: 61W Sec: 36 Twp: 9N Rng: 61W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 270 ft

18. Distance to nearest property line: 302 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 458 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		640	ALL

21. Mineral Ownership: Fee State Federal Indian Lease #: 3756608

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Township 9 North, Range 61W of the 6th P.M., Section 36: ALL

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	16	15+1/4	65	0	60	6	60	0
SURF	12+1/4	9+5/8	36	0	1,443	534	1,443	60
1ST	8+3/4	7	23	0	6,652	571	6,652	1,443
1ST LINER	6+1/4	4+1/2	11.6	5927	10,792			

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Hearing date was June 16, 2013.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Tina Taylor

Title: Regulatory Compliance Date: _____ Email: tina.taylor@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTC' located at: \\Inetpub\NetReports\policy_ntc.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400440517	DEVIATED DRILLING PLAN
400440536	DIRECTIONAL DATA
400440639	OFFSET WELL EVALUATION
400440669	WELL LOCATION PLAT

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids. Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit/Pond.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Planning	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use. Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source. Operator will participate in the Colorado Oil & Gas Association Voluntary Baseline Groundwater Quality Sampling Program. Operator will implement interim reclamation measures immediately after construction of the location to stabilize cut and fill slopes, stabilize the topsoil and spoil stockpiles, establish desirable vegetation and control weeds on the location.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.
Planning	A Form 15 Pit Report will be submitted within 30 days of construction of the fresh water storage pit.

Total: 6 comment(s)