

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 39907
LOCATION Oakley, KS
FOREMAN Kelly Gabel

FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-1-13	4595	Shady lady #1	36	12 ^s	46 ^w	Cheyenne
CUSTOMER			Cheyenne Wells Co			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
Pronghorn North to Rd 2. w to Rd 36 1 1/2 N W. 5.			399	Damon		
			528	Travis		
CITY	STATE	ZIP CODE				

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>485</u>	CASING SIZE & WEIGHT <u>8 5/8 24#</u>
CASING DEPTH <u>473</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>5'</u>
DISPLACEMENT <u>29661</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety meeting, rigged upon wildcat drilling, booked up to circulate, mixed 275 sks com 390 cc 290 gel, released plug & displaced with 29 bbl water, shut in, washed out pumps & lines rigged down.

Cement did circulate

Approx 9661 to pit

Thank You
Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54015	1	PUMP CHARGE	1150 ⁰⁰	1150 ⁰⁰
5406	75	MILEAGE	5 ²⁵	393 ⁷⁵
11045	2755K5	Class A cement	18 ⁵⁵	5101 ²⁵
1118B	517#	Bentonite	.27	139 ⁵⁹
1102	776#	Calcium chloride	.94	729 ⁴⁴
5407A	12.98	Ton mileage delivery	1 ⁷⁵	1696 ⁴¹
4432	1	8 5/8 Wooden Plug	100 ⁷⁵	100 ⁷⁵
				9311 ¹⁹
			10%	931 ¹³
				8380 ⁰⁷
			SALES TAX	
			ESTIMATED TOTAL	

Ravin 3737

2:30 PM

AUTHORIZTION

TITLE Foolpusher Willcat Drilling DATE 5-1-73

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 39930
LOCATION Oakley KS
FOREMAN Fuzz4
Milos Shaw
Colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-7-13	6378	Shady Lady #1	36	12S	46W	Cheyenne
CUSTOMER <u>Prienchon</u>			Cheyenne Wells			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			456	Tim W		
			566	Ed W		
CITY	STATE	ZIP CODE				

JOB TYPE Production HOLE SIZE 5718 HOLE DEPTH 5053 CASING SIZE & WEIGHT 5 1/2 - 15.5 #
CASING DEPTH 4992.16 DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 14.2 SLURRY VOL 1.42 WATER gal/sk _____ CEMENT LEFT in CASING - 0 -
DISPLACEMENT 118.9 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting on Wildcat #1 Flood equip - hatchdown in
Flow shoe Cent 1-3-5-7-46 Turbos 9-10-11-12-13 Port collar top of 47
Back End of 47 Csc 1/2 hr J+50. Csc on bottom 1 1/2 hrs. Pump SAGL
water, 500 gal Mud Flush, SAGL water SPS AH, SPS MH. Mix
21 SSKS OWC down 5 1/2 csg. Wash pump & lines. Drop plug and displace
120 1/2 BBL. Loss returns @ 40 BBL out work regained returns
200 1/2 @ 90 BBL out Ending list pressure 500* Land plug @ 1100*

THANKS Fuzz4 & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3400.00	3400.00
5406	85	MILEAGE	5.25	446.25
5407A	10.6 ton	Tow mileage Delivery	175	1576.25
1126	22 SSKS	OWC	23.70	5332.50
1144G	500 gal	Mud Flush	1.00	500.00
4159	1	5 1/2 - AFU Flow shoe (I)	433.75	433.75
4454	1	5 1/2 - hatchdown Assy (I)	318.25	318.25
4130	5	5 1/2 - Centralizers (W)	61.00	305.00
4136	5	5 1/2 - Turbolizers (I)	75.75	378.75
4104	1	5 1/2 - Basket (I)	290.00	290.00
4285	1	5 1/2 - Port collar (I)	2178.25	2178.25
				15160.00
				1516.00
				13644.00
			SALES TAX	
			ESTIMATED	
			TOTAL	

Ravin 3737

AUTHORIZATION Jk SA

TITLE 3

DATE 5-8-13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.