

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: WARNER 5-14

Project: COLORADO-WELD-NAD83-UTM13

Site: WARNER 5-14

Rig Name No: ECWS 7/7

Event: ABANDONMENT

Start Date: 5/28/2013

End Date: 6/18/2013

Spud Date: 2/28/2004

Active Datum: RKB @5,074.99usft (above Mean Sea Level)

UWI: 0/2/N/66/W/14/0/NWSW/6/0/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	05/28/2013		MIRU ECWS 7. TP & CP = 1300#. Control well. NDWH. NUBOP. TOO H & tally. RU Pioneer. Set CIBP at 7200. Load csg. Test csg to 1000# for 15 min. SDFN.
2	05/29/2013		RU Pioneer. Ran CBL from 7100-0. TOC @ 6450. Good cement from 4780-3370. TIH to 7193. Hydrotest tbg to 3000. RU Sanjel. Pumped 30 sx G w/ 20% silica flour. TOO H. SDFN.
3	05/30/2013		TIH. Tag at 6790. Pumped 80 BBL 9.2# mud. TOO H & LD 2000' tbg. EOT at 4805. RU Sanjel. Pumped 45 sx Type 2 cement. TOO H. SDFN.
4	05/31/2013		TIH. Tag at 4320. TOO H & LD tbg. RU Pioneer. Cut csg at 1100. LD csg. TIH to 1205 w/ tbg. RU Sanjel. Could not get returns. Pumping into at 800#. PO 4 jt. Turn tbg. RIH w/ 4 jt. Same thing. TOO H. Dry heavy mud on outside of bottom 4 jt. SDFN.
5	06/03/2013		TIH. Circ last 105' into hole. Circ for 1.5 hr. RU Sanjel. Pumped 245 sx Type 3 cement. Had good returns for first 34 BBL. Then lost returns & press up. Flowed back 15 BBL cement to tank. TBG is stuck. Worked tbg. Backed off tbg 2 jt down. SDFN.
6	06/04/2013		TIH w/ 1 1/4 tbg. Tag at 993. Circ to 1060. Tag hard cement. Circ. RU Sanjel. Pumped 120 sx Type 3 cement. Had good returns thru out job. TOO H & LD tbg. SWI. SDFN.
7	06/05/2013		NDBOP. RU Pioneer. Set 8 5/8 Thunderbird CIBP at 52'. NUBOP. Test CIBP to 1000# for 15 min. NDBOP. RDMO.
8	06/18/2013		Crew travel, safety. Dug up surface csg. Cut csg 6' below GL. Tagged @ 49'. Filled csg w 20 bags 5000# cement. Capped csg w plate containing well info. Backfilled.
9	06/18/2013		TIME ON: 10:0, ROUTE: S42, WINS: 73699, PROJECT TYPE: P&A, PROD: NB/CD, TP: N/A, CP: N/A, CHOKE: N/A, BATT #: 34002632, GATHERER: KMG, STAT #: 30100, LINE #: 14-875-4EXT, COMMENTS: P&A'd OFFLINE.