

# HSR Federal 6-36 05-123-18479 - Proposed WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

## Existing

KB: 5015  
GL: 5005

8 5/8" Surf Csg Shoe @ 762  
Base Fox Hills @ Behind Pipe

Top of Sussex @ 4550  
Base of Shannon @ 5600

TOC @ 6489

NB Top @ 7177

Nio perfs @ 7183-7185  
CD perfs @ 7396-7399

2-7/8" Prod Csg @ 7526  
TD @ 7540

## Planned

35 sx of cement

Welded Cap  
Surface plug 10'-100'  
CIBP @ 100

110 sx of cement, 8.5" caliper  
hole and 0.0636 bbl/Inft SC

cement plug from 870-560

45 sx of cement, 8.5"  
caliper % 20% excess

Stabilizer Cmmt Plug @ 1800-1900

650 sx of cement, 8.5" caliper  
and 40% excess

Cement plug @ 4350-5700  
Cut csg @ 5700'

15 sx of cement, 0.00579 bbl/Inft

Balanced cmnt plug @ 6770-7000

CIBP @ 7100

