

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400427548

Date Received:

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☒ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20120060

3. Name of Operator: PRONGHORN OPERATING LLC

4. COGCC Operator Number: 10422

5. Address: 8400 E PRENTICE AVENUE #1000

City: GREENWOOD State: CO Zip: 80111
VILLAGE

6. Contact Name: Jake Flora Phone: (720)988-5375 Fax: ()

Email: jakeflora@kfrcorp.com

7. Well Name: State of Colorado Well Number: 2

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 5522

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 16 Twp: 13S Rng: 44W Meridian: 6

Latitude: 38.915480 Longitude: -102.349740

Footage at Surface: 689 feet FNL/FSL FSL 662 feet FEL/FWL FWL

11. Field Name: SMOKY CREEK Field Number: 77560

12. Ground Elevation: 4276 13. County: CHEYENNE

14. GPS Data:

Date of Measurement: 05/13/2013 PDOP Reading: 3.1 Instrument Operator's Name: Elijah Frane

15. If well is ☐ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 33857 ft

18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1270 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MARMATON	MRTN			
MISSISSIPPIAN	MSSP			

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: 2366.12

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

ALL, 16, 13S, 44W, 6th PM

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: DRY & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	20	0	284	211	284	0
1ST	7+7/8	5+1/2	15.5	0	5,522	200	5,522	4,022
S.C. 1.1					2,500	200	2,500	1,200

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a re-entry into a drilled & abandoned wellbore. Proposed operations will include digging up the original 8-5/8" surface casing, welding an extension & flange on the casing, nipping up an annular BOP, drilling out existing abandonment cement plugs, clean out the original wellbore to the original TD of 5522', run and cement 5.5" production casing to 5522', cement upper stage per APD requirements, and test the Mississippian formation.

34. Location ID: 380191

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jake Flora

Title: Petroleum Engineer Date: _____ Email: jakeflora@kfrcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 017 06098 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTC' located at: W:\Inetpub\NetReports\policy_ntc.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400427553	MINERAL LEASE MAP
400434187	WELLBORE DIAGRAM
400442617	30 DAY NOTICE LETTER

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)