

Hamilton 2-29

Proposed Schematic

Field: WFU
County: Moffat
Township: Sec:29 , Twp:5 N, Rng:91 W
Rig:
Permit API: 0

AFE / Network #:	0
Shell Working Interest:	100%
AFE Drilling Cost: \$0	
Plan Days:	0

LAT:	
LONG:	
Ground Elevation:	6343 ft (surveyed)
RKB to Ground:	ft
RKB Elevation:	ft

Objectives:

30" Hole drilled to	90
20" pipe (0.25") set @	90
Cement to surface	

Surface

13-1/2" Hole drilled to	500
10-3/4" 40.5# J-55 STC @	500
Cement to surface	

Intermediate

9-7/8" Hole drilled to	2300
7-5/8" 29.7# P-110 LTC @	2300
Top of cement 1800' MD	

Production

6-3/4" Hole drilled to	6233
5-1/2" 17# N-80 H-511 @	6233

NOTES

Notify COGCC according to NW Notifications
Test BOPs to 2000 psi
Test 10-3/4" csg to 1500 psi for 30 min
Test 7-5/8" csg to 1500 psi for 30 min

Casing

Surface:

10 3/4" 40.5# J-55 R3 ST&C
0-500 ft

Intermediate:

7 5/8" 29.7# P-110 R3 LT&C
0-2300 ft

Production:

5 1/2" 17# N-80 R3 H511 / STL
2100-6233 ft MD

DRILLING FLUIDS

Surface: Clear Gyp Water

Hi-Vis Sweeps as needed

Intermediate: Clear Gyp Water + Air

Production: Aerated OBM or brine

TOE AT 2881' TVD / 6233' MD

HEEL AT 3130' TVD / 3680' MD