



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

# FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 39990  
LOCATION OK 104  
FOREMAN Fuzz

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
5.31.13	6378	Hanley #3	5	14S	44N	Cherokee																
CUSTOMER Pranchain			<table border="1"> <tr> <th>TRUCK #</th><th>DRIVER</th><th>TRUCK #</th><th>DRIVER</th></tr> <tr> <td>463</td><td>Cori B</td><td></td><td></td></tr> <tr> <td>460</td><td>Tim W</td><td></td><td></td></tr> <tr> <td>397</td><td>Mike P</td><td></td><td></td></tr> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	463	Cori B			460	Tim W			397	Mike P		
TRUCK #	DRIVER	TRUCK #					DRIVER															
463	Cori B																					
460	Tim W																					
397	Mike P																					
MAILING ADDRESS																						
CITY	STATE	ZIP CODE																				

JOB TYPE 2-Port Collar HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2  
CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 7/8 OTHER #1-4276  
SLURRY WEIGHT 14.2-12.5 SLURRY VOL 1.42-1.9 WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING #2-2547  
DISPLACEMENT 24.8-14 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting on ECWS. Pick up Tool closed tool to 1000'  
Est circulation. Mix 100skt OWC w/ 290cc Displace 24 BBL. Close  
Port Collar press to 1000'. Run 4 Jts. Reverse Tbs clean with 50 BBL  
water wait 2 hrs. Pull to 2547' Test closed tool to 1000'  
Establish circulation. Mix 200skt 60/40 290cc Displace 14 BBL  
close Tool and press to 1000'. Run 4 Jts reverse Tbs clean with 40  
BBL water.

Thanks Fuzz & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401B	1	PUMP CHARGE	1785.00	1785.00
5406	85	MILEAGE	5.25	446.25
5407A	13.3 ton	Ton Mileage Delivery	1.25	16.63
1131	200skt	60/40 pos	15.80	3160.00
1126	100skt	OWC	23.70	2370.00
1102	532#	Calcium Chloride	.94	500.08
1118B	344	Bentone	.27	92.88
1107		Slogral		N/A
5613	1	Squeeze Manifold	200.00	200.00
		subtotal		10544.76
		less 10%		1054.48
		subtotal		9490.28
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION Jke SA TITLE Field Sup DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

# FIELD TICKET & TREATMENT REPORT

TICKET NUMBER 39988  
LOCATION Oakley KS  
FOREMAN Fuzz

## CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-25-13	6378	Harley #3	5	14S	44W	Cherokee
CUSTOMER Pronchaw Operating LLC			chey wells Rd 43 4W			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			463	Corey D		
			693	Ed W		
CITY	STATE	ZIP CODE	Dodge City KS 67801 (2)			

JOB TYPE Production HOLE SIZE 7718 HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2 IS. S  
CASING DEPTH 5579' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT 14:2 SLURRY VOL 1.42 WATER gal/sk 6.9 CEMENT LEFT in CASING 1057  
DISPLACEMENT 132.4 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Safety meeting on wildcat #1. Float equip sent 1-5-6-31-34-72-75  
Turbo's 2-3-4-33-74 Back-Bat 32-73 P-collars Top 32-73, Rig up  
Rig pumped 135 BBL mud, no returns. Pump 500 gal mud flush  
Mix 5 SKS MH, 5 SKS AH. Mix 150 SKS OWC w/ 5# Kol-seal, 1/2 # 80# closed  
wash pump and lines, Drop plug and displace 135 1/2 BBL. 400# 1st  
800# land. Float held. Weave achieved circulation  
Shot in a head

Thanks Fuzz & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	3400 <sup>00</sup>	3400 <sup>00</sup>
5406	85	MILEAGE	525	44625
5407A	7.5 ton	Ton Mileage Delivery	175	11562
1126	160 SKS	OWC	2320	3792 <sup>00</sup>
1110A	800#	Kol-seal	156	1448 <sup>00</sup>
1107	80#	Flo-seal	297	23760
1144G	500 gal	mud Flush	100	500 <sup>00</sup>
4159	1	5 1/2 - AFU-Float shoe (w)	43325	43325
4454	1	5 1/2 - Hatchdown Wassy	31825	31825
4130	7	5 1/2 - Centralizers (w)	6100	42700
4136	5	5 1/2 - Turbolizers	7525	37825
4104	2	5 1/2 - BackBats	29000	58000
4285	2	5 1/2 - Port Collars	217825	435600
		subtotal		1543322
		less 100%		154332
		subtotal		1388990
		SALES TAX		
		ESTIMATED TOTAL		

Ravin 3737

AUTHORIZATION [Signature] TITLE MANAGING MEMBER DATE 5/25/13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

## Surface CASing

TICKET NUMBER 39971  
LOCATION Oakley, KS  
FOREMAN Kelly Gabel

# FIELD TICKET & TREATMENT REPORT CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-15-13	6378	Nalley #3	5	143	44 W	Cheyenne
CUSTOMER Pronghorn			Cheyenne Wells			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
CITY			4163	SEAN	6912	(?)
			6931	EDDIE		
				DAN		
STATE			4166	MIKE		
ZIP CODE						

JOB TYPE <u>Surface</u>	HOLE SIZE <u>17 1/2</u>	HOLE DEPTH <u>500</u>	CASING SIZE & WEIGHT <u>13 3/8 - 54 1/2 #</u>
CASING DEPTH <u>498'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>30'</u>
DISPLACEMENT <u>22 bbl</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety meeting, rigged up on Wildcat #1, hooked up to circulate, mixed 425 sls com 3% cc 2% gel, released plug & displaced with 22 bbl water, shut in, washed out pump lines rigged down.

Cement did circulate to surface

Thank You.  
Kathy Gere

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	1785 <sup>00</sup>	1785 <sup>00</sup>
5406	85	MILEAGE	5 <sup>35</sup>	446 <sup>25</sup>
11045	425 sacks	Class A cement	18 <sup>55</sup>	7883 <sup>75</sup>
1102	1199#	Calcium chloride	.94	1127 <sup>06</sup>
1118B	799#	Bentonite	1.27	215 <sup>73</sup>
5407A	20-ton	Ton mileage delivery	1487 <sup>50</sup>	2975 <sup>00</sup>
4436	1	13 <sup>3</sup> / <sub>8</sub> wooden Plug	179 <sup>75</sup>	179 <sup>75</sup>
				14,612 <sup>54</sup>
				1461 <sup>25</sup>
				13,151 <sup>29</sup>
			SALES TAX	

Ravin 3737

## AUTHORIZATION

TITLE

TITLE *Non-Member*

DATE 5-13-13

**I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.**