



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

201216

Date 4-16-13	Well Owner TRILOGY RESOURCES	Well No. 17-11	Lease WIND
County WELD	State COLORADO	Field	
Charge to CADDE DRILLING, LLC	Charge Code		For Office Use Only
Address 3450 WCR 27 UNIT # 2 (CADE-25)			
City, State FT LUTON COLORADO 80621			
Pump Truck No. 1202	Code	Bulk Truck No. 1214	Code
Type of Job	Depth	Ft. 699	To
(Surface) 8 5/8" CSG-24 #	Bottom of Surface	Ft. 689	To
Plug	Plug Landed @ 647	Ft.	Time On 1500
Production	Pipe Landed @ 689	Ft.	Time Off PLUG DOWN 1730

Reference No.	Description	Qty.	Meas.	Unit Price	Amount		
	Pump Truck Charge						
	Cement Neat ✓	450	SKS				
	Poz. Mix						
	Calcium Chloride	3%					
	Gel % Flo-Cele $\frac{1}{4}$ #Per Sack						
	Handling Charge						
	Hauling Charge						
	Additional Cement						
8 5/8"	CENTRALIZERS	3					
"	CEMENT BASKET	1					
"	GUIDE SHOE	1					
"	BAFFLE PLATE	1					
	BOX THREADLOCK	1					
	MIX RATE 4 BPM	SLURRY VOL	1.18 FT ³ /SK-WATER	TEMP	58 °		
	DISP. RATE 5 BPM	SLURRY WT	15.2 PPG				
	PLUG LANDED @ 600 PSI	TOTAL SLURRY VOL	94.5 BBL CEMENT				
Remarks: PREFLUSH w/ 20 BBL H ₂ O		Tax Reference Code		Sub Total			
DISPLACE w/ 41.1 BBL H ₂ O		State CO 2-9 %		Tax			
CIRCULATE 6 BBL CEMENT		Disc.		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		42			
1214		Bulk Truck		42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN**

Received By

Customer or His Agent