

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400420313

Date Received:

06/20/2013

PluggingBond SuretyID

20120125

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: URSA OPERATING COMPANY LLC4. COGCC Operator Number: 104475. Address: 1050 17TH STREET #2400City: DENVER State: CO Zip: 802656. Contact Name: Shauna Redican Phone: (720)508-8350 Fax: (720)508-8368Email: sredican@ursaresources.com7. Well Name: BAT Well Number: 34A-24-07-96

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 6178

## WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 24 Twp: 7S Rng: 96W Meridian: 6Latitude: 39.420840 Longitude: -108.060350

Footage at Surface: 1903 feet FNL/FSL 1966 feet FEL/FWL  
 FSL FWL

11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 5183 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 08/05/2010 PDOP Reading: 2.4 Instrument Operator's Name: Scott Aibner15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1377 FSL 1973 FEL 1377 FSL 1973 FEL  
 Bottom Hole: FNL/FSL 1377 FSL 1973 FEL  
 Sec: 24 Twp: 7S Rng: 96W Sec: 24 Twp: 7S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 258 ft18. Distance to nearest property line: 262 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 311 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	139-116	588	L 1,5&6,NENE,S2NE,S2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached mineral lease map

25. Distance to Nearest Mineral Lease Line: 54 ft

26. Total Acres in Lease: 378

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	55#	0	60	50	60	0
SURF	12+1/4	8+5/8	32#	0	1,819	451	1,819	0
1ST	7+7/8	4+1/2	11.6#	0	6,178	548	6,178	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments A Form 2A Amendment to expand the pad and add additional wells to the location was submitted on 6/13/2013. Spacing order 139-31 unit configuration includes all of Section 24, T7S, R96W excluding Lots 2, 3 & 4. TOP OF CEMENT OF 1ST STRING/PRODUCTION CASING WILL BE >500 FEET ABOVE TOP OF GAS.

34. Location ID: 422301

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Shauna Redican

Title: Permit Representative Date: 6/20/2013 Email: sredican@ursaresources.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 7/21/2013

API NUMBER

05 045 22092 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/20/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

### **Applicable Policies and Notices to Operators**

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Notice Concerning Operating Requirements for Wildlife Protection.

### **Attachment Check List**

Att Doc Num	Name
400420313	FORM 2 SUBMITTED
400422532	MINERAL LEASE MAP
400422538	30 DAY NOTICE LETTER
400422540	SURFACE AGRMT/SURETY
400435720	WELL LOCATION PLAT
400435722	DEVIATED DRILLING PLAN
400435723	DIRECTIONAL DATA

Total Attach: 7 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	No LGD or public comments. Final Review--passed.	7/18/2013 12:08:46 PM
LGD	pass, gdb	7/11/2013 5:10:09 PM
Permit	Corrected spacing order, acreage, & configuration.	7/10/2013 11:12:21 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.	6/25/2013 2:33:16 PM
Permit	Pass completeness.	6/21/2013 10:54:04 AM

Total: 5 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>