

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400439474

Date Received:

06/26/2013

PluggingBond SuretyID

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refilling ☒Sidetrack ☐3. Name of Operator: BARRETT CORPORATION* BILL4. COGCC Operator Number: 100715. Address: 1099 18TH ST STE 2300City: DENVER State: CO Zip: 802026. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420Email: mpobuda@billbarrettcorp.com7. Well Name: Greasewood Well Number: 08-18H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10670

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 18 Twp: 6N Rng: 61W Meridian: 6Latitude: 40.493764 Longitude: -104.251447

Footage at Surface: 501 feet FNL 2413 feet FEL
 FNL/FSL FEL/FWL

11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 4727 13. County: WELD

14. GPS Data:

Date of Measurement: 02/22/2011 PDOP Reading: 1.3 Instrument Operator's Name: Robert Kay15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
600 FNL 2000 FEL 600 FSL 2000 FEL
 Sec: 18 Twp: 6N Rng: 61W Sec: 18 Twp: 6N Rng: 61W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 2413 ft18. Distance to nearest property line: 1119 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2050 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-4	640	ALL

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6N-R61W Section 18: Lots 1-4, E2NW, North 20 acres of the SW, W2E2, SESE, E2NE, NESE, E2SW

25. Distance to Nearest Mineral Lease Line: 600 ft

26. Total Acres in Lease: 1340

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	42	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	430	800	0
1ST	8+3/4	7	26	0	6,726	560	6,726	0
1ST LINER	6+1/8	4+1/2	11.6	5900	10,670			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Please note that Bill Barrett Corporation (BBC) aquired this permit from EOG in July 2012. On 10/16/12 BBC recieved an approved Sundry from COGCC to change the BHL from what was originally permitted to the referenced location. I certify that there have been no changes from the existing permit.

34. Location ID: 423895

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mary Pobuda

Title: Permit Analyst Date: 6/26/2013 Email: mpobuda@billbarrettcorp.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 7/21/2013

API NUMBER

05 123 33780 00

Permit Number: _____ Expiration Date: 7/20/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
400439474	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review completed. No LGD or public comments on this refile.	7/18/2013 5:48:12 AM
Engineer	No existing wells within 500' of proposed directional.	7/15/2013 3:50:45 PM
Permit	Pass completeness.	6/27/2013 2:02:20 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>