

**FORM
2A**Rev
04/01**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400433327

Date Received:

06/13/2013

Oil and Gas Location Assessment☐ New Location☒ Amend Existing Location Location#: 416483

Submit original plus one copy. This form is to be submitted to the COGCC prior to any ground disturbance activity associated with oil and gas development operations. This Assessment may be approved as a standalone application or submitted as an informational report accompanying an Application for Permit-To-Drill, Form 2. Approval of this Assessment will allow for the construction of the below specified location; however, it does not supersede any land use rules applied by the local land use authority. This form may serve as notice to land owners and other interested parties, please see the COGCC web site at <http://colorado.gov/cogcc/> for all accompanying information pertinent to this Oil and Gas Location Assessment.

Location ID:

416483

Expiration Date:

07/20/2016☐ This location assessment is included as part of a permit application.**1. CONSULTATION**

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # _____
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

2. OperatorOperator Number: 96850Name: WPX ENERGY ROCKY MOUNTAIN LLCAddress: 1001 17TH STREET - SUITE #1200City: DENVER State: CO Zip: 80202**3. Contact Information**Name: Greg DavisPhone: (303) 606-4071Fax: (303) 629-8268email: greg.j.davis@wpxenergy.com**4. Location Identification:**Name: FederalNumber: SG 23-29County: GARFIELDQuarterQuarter: LOT 5 Section: 29 Township: 7S Range: 96W Meridian: 6 Ground Elevation: 5089

Define a single point as a location reference for the facility location. This point should be used as the point of measurement in the drawings to be submitted with this application. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 1212 feet FSL, from North or South section line, and 1368 feet FWL, from East or West section line.Latitude: 39.403494 Longitude: -108.135822 PDOP Reading: 4.0 Date of Measurement: 05/07/2009Instrument Operator's Name: Robert Kay**5. Facilities (Indicate the number of each type of oil and gas facility planned on location):**

Special Purpose Pits: <input type="text"/>	Drilling Pits: <input type="text"/>	Wells: <input type="text" value="16"/>	Production Pits: <input type="text"/>	Dehydrator Units: <input type="text"/>
Condensate Tanks: <input type="text" value="4"/>	Water Tanks: <input type="text" value="4"/>	Separators: <input type="text" value="16"/>	Electric Motors: <input type="text"/>	Multi-Well Pits: <input type="text"/>
Gas or Diesel Motors: <input type="text"/>	Cavity Pumps: <input type="text"/>	LACT Unit: <input type="text"/>	Pump Jacks: <input type="text"/>	Pigging Station: <input type="text"/>
Electric Generators: <input type="text"/>	Gas Pipeline: <input type="text" value="1"/>	Oil Pipeline: <input type="text" value="1"/>	Water Pipeline: <input type="text" value="1"/>	Flare: <input type="text"/>
Gas Compressors: <input type="text"/>	VOC Combustor: <input type="text"/>	Oil Tanks: <input type="text"/>	Fuel Tanks: <input type="text"/>	

Other: Cuttings Trench

6. Construction:

Date planned to commence construction: 01/01/2014 Size of disturbed area during construction in acres: 5.46
Estimated date that interim reclamation will begin: 09/01/2014 Size of location after interim reclamation in acres: 1.34
Estimated post-construction ground elevation: 5383 Will a closed loop system be used for drilling fluids: Yes ☒
Will salt sections be encountered during drilling: Yes ☐ No ☒ Is H2S anticipated? Yes ☐ No ☒
Will salt (>15,000 ppm TDS Cl) or oil based muds be used: Yes ☐ No ☒
Mud disposal: Offsite ☐ Onsite ☒ Method: Land Farming ☐ Land Spreading ☐ Disposal Facility ☐
Other: Re-use and evaporation

7. Surface Owner:

Name: _____ Phone: _____
Address: _____ Fax: _____
Address: _____ Email: _____
City: _____ State: _____ Zip: _____ Date of Rule 306 surface owner consultation: _____
Surface Owner: ☐ Fee ☐ State ☒ Federal ☐ Indian
Mineral Owner: ☐ Fee ☐ State ☒ Federal ☐ Indian
The surface owner is: ☒ the mineral owner ☒ committed to an oil and gas lease
☒ is the executer of the oil and gas lease ☐ the applicant
The right to construct the location is granted by: ☒ oil and gas lease ☐ Surface Use Agreement ☐ Right of Way
☐ applicant is owner
Surface damage assurance if no agreement is in place: ☐ \$2000 ☐ \$5000 ☐ Blanket Surety ID _____

8. Reclamation Financial Assurance:

☐ Well Surety ID: 20030107 ☐ Gas Facility Surety ID: _____ ☐ Waste Mgmt. Surety ID: _____

9. Cultural:

Is the location in a high density area (Rule 603.b.): Yes ☐ No ☒
Distance, in feet, to nearest building: 6923, public road: 4140, above ground utility: 5465,
railroad: 6390, property line: 1353

10. Current Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP
Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____
Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

11. Future Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP
Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____
Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

12. Soils:

List all soil map units that occur within the proposed location. Attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.gov/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 66 Torriorthents-Camborthids-Rock Outcrop, Complex Steep

NRCS Map Unit Name: 47 Nihill Channery Loam, 6 to 25% slopes

NRCS Map Unit Name:

13. Plant Community:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☒

Plant species from: ☐ NRCS or, ☒ field observation Date of observation: 05/07/2009

List individual species: Juniper, Sage, Native Grasses

Check all plant communities that exist in the disturbed area.

- ☐ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
☒ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
☒ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
☒ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
☐ Alpine (above timberline)
☐ Other (describe):

14. Water Resources:

Rule 901.e. may require a sensitive area determination be performed. If this determination is performed the data is to be submitted with the Form 2A.

Is this a sensitive area: ☐ No ☒ Yes Was a Rule 901.e. Sensitive Areas Determination performed: ☐ No ☒ Yes

Distance (in feet) to nearest surface water: 153, water well: 7567, depth to ground water: 6

Is the location in a riparian area: ☒ No ☐ Yes Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes

Is the location within a Rule 317B Surface Water Supply Area buffer zone:

☒ No ☐ 0-300 ft. zone ☐ 301-500 ft. zone ☐ 501-2640 ft. zone

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: ☐ No ☐ Yes

15. Comments:

This Form 2A is a re-file of the original which has expired. The location is currently not built, but will be in the future. Attachments were included with the original 2A. There have been no changes to the original Form 2A.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: Date: 06/13/2013 Email: greg.j.davis@wpenergy.com

Print Name: Greg Davis Title: Supervisor Permits

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 7/21/2013

**CONDITIONS OF
APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

GROUNDWATER BASELINE SAMPLING COA:

Operator shall comply with Rule 609. STATEWIDE GROUNDWATER BASELINE SAMPLING AND MONITORING.

PIPELINE COAs:

Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service.

Operator must implement best management practices to contain any unintentional release of fluids along all portions of the surface pipeline route where temporary pumps and other necessary equipment are located.

Operator must routinely inspect the entire length of the surface pipeline to ensure integrity.

Operator must ensure 110 percent secondary containment for any potential volume of fluids that may be released from the surface pipeline at all stream, intermittent stream, ditch, and drainage crossings.

Operator will utilize, to the extent practical, all existing access and other public roads, and/or existing pipeline right-of-ways, when placing/routing the surface pipelines. This will reduce surface disturbance and fragmentation of wildlife habitat in the area.

GENERAL SITE COAs:

Any pit that will hold liquids [if constructed], must be lined or a closed loop system (which has been indicated on the Form 2A by Williams) must be implemented during drilling.

Operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures sufficiently protective of nearby surface water. If fluids are conveyed via pipeline, operator must implement best management practices to contain any unintentional release of fluids.

The moisture content of any drill cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, if the drill drill cuttings are to be onsite, must also meet the applicable standards of table 910-1.

The location is in an area of moderate run off/run-on potential; therefore the pad shall be constructed to prevent any stormwater run-on and/or stormwater runoff.

No portion of any pit that will be used to hold liquids shall be constructed on fill material, unless the pit and fill slope are designed and certified by a professional engineer, subject to review and approval by the director prior to construction of the pit. The construction and lining of the pit shall be supervised by a professional engineer or their agent. The entire base of the pit must be in cut.

Notify the COGCC 48 hours prior to start of pad construction, rig mobilization, spud, and start of hydraulic stimulation operations using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).

The location is in an area of moderate to high run-on/run-off potential; therefore standard stormwater BMPs must be implemented at this location to insure compliance with CDPHE and COGCC requirements and to prevent any stormwater run-on and /or stormwater run-off.

Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline, storage vessel, or lined pit (only if an amended Form 2A has been submitted/approved and a Form 15 Earthen Pit Permitted has been submitted/approved) located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area with additional downgradient perimeter berming. The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released material.

Berms or other containment devices shall be constructed to be sufficiently impervious (preferably corrugated steel with poly liner) to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.

Attachment Check List

Att Doc Num	Name
400433327	FORM 2A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comments. Final Review--passed.	7/18/2013 12:30:54 PM
Permit	Both APD's on this location have been abandoned.	7/10/2013 2:04:55 PM
OGLA	PREVIOUS FORM 2A#400034958 COAs: Operator must implement best management practices to contain any unintentional release of fluids. Location is in a sensitive area because of close proximity to surface water, therefore, operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations.	6/18/2013 8:54:02 PM
OGLA	Initiated/Completed OGLA Form 2A review on 06-18-13 by Dave Kubeczko; previously submitted Form 2A#400034958 (approved on 10-15-10); Facility ID#416483; same COAs apply: fluid containment, spill/release BMPs; added lined pits, no pit in fill, sediment control, moisture content cuttings, flowback to tanks, tank berming, GW sampling, pipeline COAs on permit; no CPW; passed OGLA Form 2A review on 07-17-13 by Dave Kubeczko; fluid containment, spill/release BMPs, lined pits, no pit in fill, sediment control, moisture content cuttings, notification, flowback to tanks, tank berming, GW sampling, and pipeline COAs.	6/18/2013 8:54:01 PM
Permit	Inserted Surety ID and notified opr. Form passes completeness.	6/17/2013 3:02:06 PM
Permit	Returned to draft: 1) Operator should check "the surface owner has signed oil and gas lease" and is "executor". 2) Operator should add coment that this refile has no changes to original 2A.	6/14/2013 10:10:47 AM

Total: 6 comment(s)

BMP

<u>Type</u>	<u>Comment</u>