

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400435768

Date Received:

06/19/2013

PluggingBond SuretyID

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Venessa Langmacher Phone: (303)312-8172 Fax: (303)291-0420

Email: vlangmacher@billbarrettcorp.com

7. Well Name: Circle B Well Number: 6-66-9-0461BH

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11666

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 9 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.509280 Longitude: -104.784300

Footage at Surface: 262 feet FNL 2297 feet FWL

11. Field Name: Eaton Field Number: 19350

12. Ground Elevation: 4816 13. County: WELD

14. GPS Data:

Date of Measurement: 05/15/2013 PDOP Reading: 1.2 Instrument Operator's Name: Wyatt Hall

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
550 FNL 2230 FWL 500 FSL 2230 FWL
Sec: 9 Twp: 6N Rng: 66W Sec: 9 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 249 ft

18. Distance to nearest property line: 262 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 150 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-780	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See lease map attached.

25. Distance to Nearest Mineral Lease Line: 500 ft

26. Total Acres in Lease: 480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16	65	0	60	50	60	0
SURF	13+1/2	9+5/8	36	0	800	430	800	0
1ST	8+3/4	7	26	0	7,445	620	7,445	600
1ST LINER	6+1/8	4+1/2	11.6	6700	11,666			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This well is an exception location to Rules 318Aa and 318Ac.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Venessa Langmacher

Title: Sr Permit Analyst

Date: 6/19/2013

Email: vlangmacher@billbarrettcorp.co

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 7/21/2013

API NUMBER

05 123 37696 00

Permit Number: _____ Expiration Date: 7/20/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements per Rule 318A.

1)Provide notice of MIRU via an electronic Form 42.

2)Comply with Rule 317.i and provide cement coverage to a minimum of 200' above the Niobrara. Verify cement coverage with a cement bond log per 317.o.

Operator acknowledges the proximity of the A&N Farms #22-9 API# 123-13999, A&N Farms #21-9 API# 123-13983, and Lovely #1 API# 123-12684. Operator agrees to: provide mitigation option 1, 2 or 3 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OTHER – AS SPECIFIED BY PERMIT CONDITION") stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400435768	FORM 2 SUBMITTED
400435772	DIRECTIONAL DATA
400435775	EXCEPTION LOC REQUEST
400435777	DEVIATED DRILLING PLAN
400435779	PLAT
400436195	LEASE MAP
400436196	OFFSET WELL EVALUATION

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	The spacing was approved on 6/17/2013 - Docket 1306-SP-87. Final review complete.	7/16/2013 2:05:52 PM
Engineer	Evaluated offset wells for adequate isolation.	6/27/2013 2:51:41 PM
Permit	Corrected surface and minerals to reflect that applicant owns the surface and has leased the minerals. Ready to pass pending public comment 7/11/13.	6/27/2013 12:48:56 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>