

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400386352

Date Received:

05/30/2013

PluggingBond SuretyID

20030009

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Liz Lindow Phone: (303)228-4342 Fax: (303)228-4286

Email: llindow@nobleenergyinc.com

7. Well Name: Wells Ranch AA Well Number: 27-79HN

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 14695

## WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 21 Twp: 6N Rng: 63W Meridian: 6

Latitude: 40.474540 Longitude: -104.434020

Footage at Surface: 1749 feet FNL/FSL 426 feet FEL/FWL  
 FNL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4727 13. County: WELD

## 14. GPS Data:

Date of Measurement: 10/19/2012 PDOP Reading: 1.6 Instrument Operator's Name: Adam Kelly

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 2416 FNL 4 FWL 535 FSL 1 FWL  
 Sec: 22 Twp: 6N Rng: 63W Sec: 27 Twp: 6N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1723 ft

18. Distance to nearest property line: 426 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 585 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		560	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

E2, W2 of Sec. 21, T6N R63W and other leases. Horizontal wellbore crosses multiple lease lines within drilling and spacing unit. Distance to mineral lease line is 0', distance to unit boundary is 535'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 627

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility

Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16	0	0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	890	410	890	0
1ST	8+3/4	7	26	0	7,014	480	7,014	0
1ST LINER	6+1/8	4+1/2	11.6	6864	14,695			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. THE PRODUCTION LINER WILL BE HUNG OFF INSIDE 7" CASING. UNIT CONFIGURATION = T6N R63W Sec 21: SENE, E2SE; Se. 22: SWNW, W2SW; Sec. 27: W2W2; Sec. 28: E2E2, 560 acres. Wellhead is to be located outside of a GWA drilling window. Noble requests an exception location to 318Aa, 318Ac. Exception requests and waivers attached.

34. Location ID: 310693

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Liz Lindow

Title: Regulatory Analyst

Date: 5/30/2013

Email: llindow@nobleenergyinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_

Director of COGCC

Date: 7/21/2013

#### API NUMBER

05 123 37717 00

Permit Number: \_\_\_\_\_

Expiration Date: 7/20/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) Provide cement coverage to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Applicable Policies and Notices to Operators**

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

### **Attachment Check List**

Att Doc Num	Name
400386352	FORM 2 SUBMITTED
400386373	30 DAY NOTICE LETTER
400386374	EXCEPTION LOC WAIVERS
400386375	WELL LOCATION PLAT
400392464	DEVIATED DRILLING PLAN
400392465	DIRECTIONAL DATA
400426717	OFFSET WELL EVALUATION
400426723	EXCEPTION LOC REQUEST
400426732	PROPOSED SPACING UNIT

Total Attach: 9 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final review completed. No LGD or public comments.	7/17/2013 6:47:21 AM
Engineer	Evaluated any existing wells within 500' of proposed directional.	6/27/2013 2:09:52 PM
Permit	Form 2A doc. # 400386273 still in DRAFT at the time. Need to verify footages when the form 2A is submitted.	6/3/2013 10:47:58 AM

Total: 3 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>