

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400434924

Date Received:

07/22/2013

PluggingBond SuretyID

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()

Email: liz.lindow@pdce.com

7. Well Name: Harvesters Resources Well Number: 15U-443

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11681

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 15 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.494680 Longitude: -104.756200

Footage at Surface: 330 feet FNL/FSL 578 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4815 13. County: WELD

14. GPS Data:

Date of Measurement: 05/17/2013 PDOP Reading: 1.3 Instrument Operator's Name: Tom Carlson

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 734 FNL 630 FEL 500 FSL 630 FEL 500  
Bottom Hole: FNL/FSL 500 FSL 630 FEL 500  
Sec: 15 Twp: 6N Rng: 66W Sec: 15 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 300 ft

18. Distance to nearest property line: 318 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 39 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| CODELL                 | CODL           |                         | 160                           | GWA                                  |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

E2NE of Sec 15 T6N R66W, see attached mineral lease map. Horizontal wellbore crosses multiple lease lines within drilling and spacing unit. Distance to mineral lease line is 0', distance to unit boundary is 500'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 78

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF        | 12+1/4       | 9+5/8          | 36    | 0             | 875           | 830       | 875     | 0       |
| 1ST         | 8+3/4        | 7              | 26    | 0             | 7,818         | 650       | 7,818   | 500     |
| 1ST LINER   | 6+1/8        | 4+1/2          | 11.6  | 6506          | 11,681        |           |         |         |

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 160 acres, E2E2 of Sec 15 T6N R66W. Proposed spacing unit map and 30-day certificate is attached. Distance to nearest well measured to via the Anti-Collision Report in the Deviated Drilling plan.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Liz Lindow

Title: Regulatory Analyst Date: 7/22/2013 Email: liz.lindow@pdce.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy\_NTO' located at: W:\Inetpub\NetReports\policy\_nto.rdl. Please check th

### Attachment Check List

| Att Doc Num | Name                   |
|-------------|------------------------|
| 400434924   | FORM 2 SUBMITTED       |
| 400445672   | WAIVERS                |
| 400445673   | PROPOSED SPACING UNIT  |
| 400445674   | WELL LOCATION PLAT     |
| 400445675   | DEVIATED DRILLING PLAN |
| 400445677   | 30 DAY NOTICE LETTER   |
| 400445678   | EXCEPTION LOC REQUEST  |
| 400445679   | EXCEPTION LOC WAIVERS  |
| 400445682   | DIRECTIONAL DATA       |
| 400452258   | OFFSET WELL EVALUATION |
| 400452959   | MINERAL LEASE MAP      |

Total Attach: 11 Files

### General Comments

| <u>User Group</u> | <u>Comment</u>  | <u>Comment Date</u>      |
|-------------------|---|--------------------------|
| Permit            | Back to draft for clarification on 78 Acres and... except a small portion in the S2SESESENE and NWNWNENE. | 7/23/2013<br>10:14:35 AM |

Total: 1 comment(s)

### BMP

| <u>Type</u>                    | <u>Comment</u>  |
|--------------------------------|---|
| Drilling/Completion Operations | Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012. The Colorado Oil and Gas Conservation Commission (COGCC) has established this Policy Regarding Bradenhead Monitoring During Hydraulic Fracturing Treatments ("Treatment") in the Greater Wattenberg Area ("GWA") pursuant to COGCC 207.a. ("Policy"). This Policy applies to oil and gas operations in the GWA as defined by the COGCC Rules of Practice and Procedure.  |
| Drilling/Completion Operations | Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5. |

Total: 2 comment(s)