

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400437291

Date Received:

06/21/2013

PluggingBond SuretyID

20120060

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

3. Name of Operator: PRONGHORN OPERATING LLC

4. COGCC Operator Number: 10422

5. Address: 8400 E PRENTICE AVENUE #1000

City: GREENWOOD VILLAGE State: CO Zip: 80111

6. Contact Name: Jake Flora Phone: (720)988-5375 Fax: ()

Email: jakeflora@kfrcorp.com

7. Well Name: Evan Well Number: 2

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 5800

## WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 7 Twp: 14S Rng: 44W Meridian: 6

Latitude: 38.854240 Longitude: -102.376250

Footage at Surface: 731 feet FNL/FSL FNL 1856 feet FEL/FWL FEL

11. Field Name: SPUR Field Number: 78800

12. Ground Elevation: 4295 13. County: CHEYENNE

### 14. GPS Data:

Date of Measurement: 06/14/2013 PDOP Reading: 2.1 Instrument Operator's Name: Keith Westfall

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 731 ft

18. Distance to nearest property line: 731 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1223 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MARMATON	MRTN			
MISSISSIPPIAN	MSSP			
TOPEKA	TOPK			

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NE/4 & NENW, 7, 14S, 44W, 6

25. Distance to Nearest Mineral Lease Line: 731 ft 26. Total Acres in Lease: 200

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: DRY & BURY

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	17+1/2	13+3/8	54	0	400	300	400	0
1ST	12+1/4	8+5/8	24	0	1,700	100	1,700	1,250
2ND	7+7/8	5+1/2	15.5	0	5,800	150	5,800	4,600
S.C. 2.1					4,100	100	4,100	3,400
S.C. 2.2					2,500	250	2,500	1,000

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments No conductor casing will be set.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jake Flora

Title: Petroleum Engineer Date: 6/21/2013 Email: jakeflora@kfrcorp.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 7/23/2013

#### API NUMBER

05 017 07759 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/22/2015

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice prior to spud via electronic Form 42.
- 2) If production casing is set provide cement coverage to at least 200' above the Shawnee and stage cement Cheyenne/Dakota (2500'-1900' minimum). Run and submit CBL to verify cemented intervals.
- 3) If well is a dry hole set plugs at the following depths: 40 sks cement +/- 50' above the Spergen, 40 sks cement +/- 50' above the Morrow, 40 sks cement +/- 50' above the Shawnee, 40 sks cement across any DST w/ show, 40 sks cement at 2500' up, 40 sks cement at 1900' up, 50 sks cement from 50' below surface casing shoe up into surface casing, 15 sks cement in top of surface casing, cut 4 ft below GL, weld on plate, 5 sks cement each in rat hole and mouse hole.
- 4) Monitor gas emissions during operations and comply with Reporting Hydrogen Sulfide (H2S) Notice to Operators and Rule 607.

**Attachment Check List**

Att Doc Num	Name
400437291	FORM 2 SUBMITTED
400437292	PLAT
400437293	SURFACE AGRMT/SURETY
400437294	MINERAL LEASE MAP

Total Attach: 4 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Final review completed; no LGD or public comment received.	7/22/2013 10:42:11 AM
Permit	The well location falls within an area that potentially may have measureable levels of H2S gas.	6/21/2013 10:08:52 AM
Permit	Corrected Mineral Lease Description as per Operator.	6/21/2013 8:21:47 AM

Total: 3 comment(s)

**BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>