

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400438753

Date Received:

06/27/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Alexis Bidgood Phone: (720)876-3074 Fax: ()

Email: Alexis.Bidgood@encana.com

7. Well Name: Rose Well Number: 22-6B (K22W)

8. Unit Name (if appl): Middleton Creek Unit Number: COC068997
X

9. Proposed Total Measured Depth: 10327

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 22 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.430627 Longitude: -107.761565

Footage at Surface: 2377 feet FNL/FSL 2218 feet FEL/FWL 2218 feet
FSL FWL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 6950 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 03/08/2013 PDOP Reading: 1.4 Instrument Operator's Name: Stacy Stewart

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL
1569 FNL 1322 FWL 1569 FNL 1322 FWL
Sec: 22 Twp: 7S Rng: 93W Sec: 22 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3458 ft

18. Distance to nearest property line: 363 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-83		
WILLIAMS FORK	WMFK	191-83		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7S, R93W, 6th P.M.; Section 10: S2SW, E2SE, NWSE; Section 11: SWNW, W2SW, SESW; Section 14: E2W2, SE, S2NE; Section 15: W2, SWNE, W2SE; Section 16: E2NE; Section 22: NWNW, E2NW, N2SW; Section 32: W2SW

25. Distance to Nearest Mineral Lease Line: 1322 ft 26. Total Acres in Lease: 1560

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24+0/0	16+0/0	.25" Wall	0	60	100	60	0
SURF	12+1/4	9+5/8	36	0	1,135	426	1,135	0
1ST	7+7/8	4+1/2	11.6	0	10,327	761	10,327	6,694

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Production Casing TOC will be set at least 200' above the Mesa Verde. Conductor and Surface Casing will be run to Surface.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Alexis Bidgood

Title: Permitting Analyst Date: 6/27/2013 Email: Alexis.Bidgood@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 7/26/2013

API NUMBER

05 045 22120 00

Permit Number: _____ Expiration Date: 7/25/2015

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

(3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.

Applicable Policies and Notices to Operators

Mamm Creek Field Area Notice to Operators.

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field).

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400438753	FORM 2 SUBMITTED
400439521	DEVIATED DRILLING PLAN
400439522	SURFACE AGRMT/SURETY
400439524	WELL LOCATION PLAT
400439527	DIRECTIONAL DATA

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 70 FEET DEEP.	7/2/2013 10:40:29 AM
Permit	Pending other approvals. Corrected TPZ footage with Operator consent. Changed distance to mineral lease line to fall in line with Spacing Order 191-83 " anywhere upon Application lands but no closer than 100/200' to Federal Unit boundaries."	6/28/2013 1:17:54 PM
Permit	Passed completeness.	6/28/2013 8:57:59 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Pre-Construction	Wattles, Silt Fence, Vegetation Buffers, Slash, Topsoil Windrows (diversions & ROP's), Scheduling, Phased Construction
Wildlife	Minimize the number, length and footprint of oil & gas development roads Use existing routes where possible Combine utility infrastructure planning (gas, electric & water) when possible with roadway planning to avoid separate utility corridors Coordinate Employee transport when possible Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors. Maximize use of state-of-the-art drilling technology (e.g., high efficiency rigs, coiled-tubing unit rigs, closed-loop or pitless drilling, etc.) to minimize disturbance.
Construction	(Not all are used all the time) Terminal Containment, Diversions, Run-On Protection, Tracking, Benching, Terracing, ECM (Erosion Control Mulch), ECB (Erosion Control Blanket), Check Dams, Seeding, Mulching, Water Bars, Stabilized Unpaved Surfaces (Gravel), Stormwater & Snow Storage Containment, Scheduling, Phased Construction, Temporary Flumes, Culverts with inlet & outlet protection, Rip Rap, TRM (Turf Reinforcement Mats), Maintenance, Scheduling, Phased Construction, Fueling BMP's, Waste Management BMP's, Materials Handling BMP's
Interim Reclamation	Maintenance Revegetation Monitoring BMP maintenance & monitoring Weed Management

Total: 4 comment(s)