

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400447464

Date Received:

07/25/2013

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()

Email: erin.hochstetler@encana.com

7. Well Name: Grant Hurt Well Number: 1B-14H G268

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 14379

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 14 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.139280 Longitude: -104.966700

Footage at Surface: 2449 feet FNL/FSL FNL 1589 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4888 13. County: WELD

14. GPS Data:

Date of Measurement: 07/01/2013 PDOP Reading: 1.5 Instrument Operator's Name: JOHN RICE

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 1962 FNL 2389 FEL 460 FNL 2229 FEL
 Sec: 14 Twp: 2N Rng: 68W Sec: 11 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1364 ft

18. Distance to nearest property line: 205 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 64 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached mineral lease map. Horizontal Wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is at least 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 142

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	7,557	427	7,557	500
2ND	6+1/8	4+1/2	13.5	0	14,379	271	14,379	7,257

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Encana requests the approval of a 318A.a.(1) and 318A.c(1) exception location as the well head is to be located outside of a GWA drilling window and further than 50' from an existing well. Request letter and waivers attached. This well is closer than 150' to the nearest permitted or producing BHL. A 318A.m. variance request letter and waivers are attached. Encana requests the approval of the omission of open hole logs; request letter attached. Proposed spacing unit is T2N R68W Section 11: E/2W/2, W/2E/2 Section 14: E/2NW/4, W/2NE/4. The distance to nearest well permitted/completed in the same formation (BHL) is the Hurt 34-11, API # 05-123-24868.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Erin Hochstetler

Title: Permitting Technician Date: 7/25/2013 Email: erin.hochstetler@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\natpub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400447464	FORM 2 SUBMITTED
400447552	DEVIATED DRILLING PLAN
400447553	WELL LOCATION PLAT
400447554	DIRECTIONAL DATA
400453171	OFFSET WELL EVALUATION
400453172	30 DAY NOTICE LETTER
400453173	OTHER
400453174	PROPOSED SPACING UNIT
400453176	EXCEPTION LOC REQUEST
400453177	EXCEPTION LOC REQUEST
400453179	EXCEPTION LOC WAIVERS
400455706	MINERAL LEASE MAP

Total Attach: 12 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Missing waste management plan. Back to draft.	7/26/2013 12:22:59 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	- Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
Drilling/Completion Operations	- Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.

Total: 2 comment(s)