

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400457116

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling   
Sidetrack

PluggingBond SuretyID

20090067

3. Name of Operator: WIEPKING-FULLERTON ENERGY LLC 4. COGCC Operator Number: 96340

5. Address: 4600 S DOWNING ST  
City: ENGLEWOOD State: CO Zip: 80113

6. Contact Name: Jack Fincham Phone: (303)906-3335 Fax: (303)761-9067  
Email: fincham4@msn.com

7. Well Name: Albatross-State Well Number: # 1

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8400

## WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 36 Twp: 9S Rng: 56W Meridian: 6  
Latitude: 39.216950 Longitude: -103.619230

Footage at Surface: 660 feet FNL/FSL 660 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5261.32 13. County: LINCOLN

### 14. GPS Data:

Date of Measurement: 06/20/2013 PDOP Reading: 2.2 Instrument Operator's Name: Keith Westfall

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_  
Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 3350 ft

18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1280 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
MISSISSIPPIAN	MSSP			
PENNSYLVANIAN	PENN			

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: 9361.7

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

All, Sec. 36, T9S, R56W

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: Backfill when dry

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	200	300	0
1ST	7+7/8	5+1/2	17	0	8,400	300	8,400	0

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments No Conductor casing will be used.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jack Fincham

Title: Agent Date: \_\_\_\_\_ Email: fincham4@msn.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY: \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy\_MTC' located at: W:\testpub\Net\Reports\policy\_etc.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400457233	30 DAY NOTICE LETTER
400457244	WELL LOCATION PLAT
400457252	TOPO MAP
400457260	SURFACE AGRMT/SURETY
400457849	OTHER

Total Attach: 5 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	<p>BMP Plan</p> <p>Wiepking-Fullerton Energy, L.L.C. 4600 S. Downing St. Englewood, CO 80113 303-789-1798 303-761-9067 (fax)</p> <p>Certification to Discharge Under CDPS General Permit COR-03000 Stormwater Discharges Associated with Construction</p> <p>Certification Number COR 39788</p> <p>Albatross-State # 1 well T9S, R56W Sec. 36: SW1/4SW1/4 Lincoln County, Colorado</p> <p>Description of Well Site and Construction Area 1-4 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. A shallow surface water depression, which is dry, is located approximately 475' Southeast of the well pad. A dirt brim will be installed on the East and South side of the well pad to protect this surface water area. Surface Roughening will be used on low side of drill site to reduce speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeding. Drilling pits closed and reclaimed within 3 months weather permitting. Topsoil will be separated and spread on drill site as final operation before reseeding operations which will be completed within 6 months weather permitting. To prevent soil erosion site will be disked and straw crimped in or manure spread.</p> <p>Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.</p> <p>Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.</p>

Total: 1 comment(s)