

MAGNA ENERGY SERVICES, LLC
17509 County Road 14,
Ft. Morgan, Colorado 80701
(970)-867-9007 or (970)-867-8374 (Fax)
Job Log

Date: 5-9-12

Operator: Slawson Exploration Company Inc

Well name: Mousetrap 36-11-66

Location: Sec. 36, T11N, R66W

County: Weld County, CO

MIRU P&A Equipment

Load hole

TIH with 1.5" coil tubing to 345'

Establish circulation rate

Mix and pump 45 sxs of 15.8# Class "G" cement "Neat"

Displace plug with 3 bbl.

TOH

TIH to 191' and tag TOC

TOH

TIH with 1" to 50' and pump 20 sxs of 15.8# Class "G" cement "Neat"

TOH

Dig out wellhead and cut casing 4' below ground level

Weld cap with legal information on

RDMO

Cementing contractor: Magna Energy Services, LLC

Cementing contractor supervisor: Brandon Chappel

Company representative: Don Smith