

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400445644

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refilling ☐

Sidetrack ☐

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()

Email: erin.hochstetler@encana.com

7. Well Name: File Well Number: 3C-32H K268

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 13500

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 32 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.092570 Longitude: -105.031180

Footage at Surface: 1757 feet FNL/FSL 1603 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4957 13. County: WELD

14. GPS Data:

Date of Measurement: 05/22/2013 PDOP Reading: 2.4 Instrument Operator's Name: JOHN RICE

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 919 FSL 460 FWL 460 FEL/FWL 750 FWL FWL
Sec: 32 Twp: 2N Rng: 68W Sec: 5 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 261 ft

18. Distance to nearest property line: 266 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 63 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		240	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached mineral lease map. Horizontal Wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is at least 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 256

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	7,805	442	7,805	500
2ND	6+1/8	4+1/2	13.5	0	13,499	228	13,499	7,505

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Encana requests the approval of a 318A.a.(1) and 318A.c(1) exception location as the well head is to be located outside of a GWA drilling window and further than 50' from an existing well. Request letter and waivers attached. This well is closer than 150' to the nearest permitted or producing BHL. A 318A.m. variance request letter and waivers are attached. Encana requests the approval of the omission of open hole logs; request letter attached. Proposed spacing unit is W/2SW/4 Section 32, W/2W/2 Section 5. The distance to nearest well permitted/completed in the same formation (BHL) is the Ray Nelson 14-32, API # 05-123-25515.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Erin Hochstetler

Title: Permitting Technician Date: _____ Email: erin.hochstetler@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\natpub\Net\Reports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400445727	WELL LOCATION PLAT
400445728	DEVIATED DRILLING PLAN
400445730	DIRECTIONAL DATA
400450157	OFFSET WELL EVALUATION
400450159	30 DAY NOTICE LETTER
400450160	OTHER
400450161	PROPOSED SPACING UNIT
400450163	VARIANCE REQUEST
400450164	EXCEPTION LOC REQUEST
400450165	EXCEPTION LOC WAIVERS
400456309	MINERAL LEASE MAP

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
Drilling/Completion Operations	Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.

Total: 2 comment(s)