

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400445646

Date Received:

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC4. COGCC Operator Number: 1001855. Address: 370 17TH ST STE 1700City: DENVER State: CO Zip: 80202-56326. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()Email: erin.hochstetler@encana.com7. Well Name: File Well Number: 3E-32H K268

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 13918

## WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 32 Twp: 2N Rng: 68W Meridian: 6Latitude: 40.092570 Longitude: -105.031110

Footage at Surface: 1757 feet FNL/FSL 1623 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 9075012. Ground Elevation: 4958 13. County: WELD

## 14. GPS Data:

Date of Measurement: 05/22/2013 PDOP Reading: 2.4 Instrument Operator's Name: JOHN RICE15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1297 FSL 1332 FEL/FWL 460 FSL 1450 FEL/FWL FWL  
 Sec: 32 Twp: 2N Rng: 68W Sec: 5 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 281 ft18. Distance to nearest property line: 286 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 232 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached mineral lease map. Horizontal Wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is at least 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 256

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	7,712	437	7,712	500
2ND	6+1/8	4+1/2	13.5	0	13,918	248	13,918	7,412

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Encana requests the approval of a 318A.a.(1) and 318A.c(1) exception location as the well head is to be located outside of a GWA drilling window and further than 50' from an existing well. Request letter and waivers attached. Encana requests the approval of the omission of open hole logs; request letter attached. Proposed spacing unit is SW/4 Section 32, W/2 Section 5. The distance to nearest well permitted/completed in the same formation (BHL) is the Schriener #11-5, API # 05-123-21067.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Erin Hochstetler

Title: Permitting Technician Date: \_\_\_\_\_ Email: erin.hochstetler@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntPolicy\_NTC' located at: \\Westpub\Net\Reports\policy\_ntc.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400445785	WELL LOCATION PLAT
400445786	DEVIATED DRILLING PLAN
400445787	DIRECTIONAL DATA
400450183	OFFSET WELL EVALUATION
400450185	30 DAY NOTICE LETTER
400450186	OTHER
400450187	PROPOSED SPACING UNIT
400450188	EXCEPTION LOC REQUEST
400450189	EXCEPTION LOC WAIVERS
400456320	MINERAL LEASE MAP

Total Attach: 10 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

### BMP

Type	Comment
Drilling/Completion Operations	Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.
Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.

Total: 2 comment(s)