

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400447633

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐

PluggingBond SuretyID

20090078

3. Name of Operator: PDC ENERGY INC4. COGCC Operator Number: 691755. Address: 1775 SHERMAN STREET - STE 3000City: DENVER State: CO Zip: 802036. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()Email: liz.lindow@pdce.com7. Well Name: Thornton Well Number: 15Y-414

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12024

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 15 Twp: 7N Rng: 66W Meridian: 6Latitude: 40.571030 Longitude: -104.755880

Footage at Surface: 1115 feet FNL/FSL 466 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 9075012. Ground Elevation: 4921 13. County: WELD

14. GPS Data:

Date of Measurement: 06/13/2013 PDOP Reading: 2.0 Instrument Operator's Name: Brian Boniface15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 179 FSL 734 FEL 200 FSL 500 FEL FWL
 Bottom Hole: FNL/FSL 200 FSL 500 FEL FWL
 Sec: 15 Twp: 7N Rng: 66W Sec: 15 Twp: 7N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 204 ft18. Distance to nearest property line: 151 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 872 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached mineral lease map. Horizontal wellbore cross multiple leases within drilling and spacing unit. Distance to mineral lease line is 0'. Distance to unit boundary is 500'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 155

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	875	830	875	0
1ST	8+3/4	7	26	0	8,090	650	8,090	500
1ST LINER	6+1/8	4+1/2	11.6	6782	12,024			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments 7" casing string will be cemented to at least 200' above Niobrara, around 500' from surface. CBL will only be run in the vertical section of the wellbore. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waivers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, S2S2 of Sec 15 and N2N2 of Sec 22 T7N R66W. Proposed spacing unit map and 30-day certificate is attached. Distance to nearest well measured to the Herrell 17-22.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Liz Lindow

Title: Regulatory Analyst Date: _____ Email: liz.lindow@pdce.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTO' located at: W:\Inetpub\NetReports\policy_nto.rdl. Please check th

Attachment Check List

Att Doc Num	Name
400447655	DEVIATED DRILLING PLAN
400447656	WELL LOCATION PLAT
400447657	30 DAY NOTICE LETTER
400447658	EXCEPTION LOC WAIVERS
400447661	DIRECTIONAL DATA
400447676	PROPOSED SPACING UNIT
400447677	EXCEPTION LOC REQUEST
400457875	OFFSET WELL EVALUATION
400457901	MINERAL LEASE MAP

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)