

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400337687

Date Received:

11/05/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10110

4. Contact Name: Shannon Hartnett

2. Name of Operator: GREAT WESTERN OPERATING COMPANY LLC

Phone: (303) 830-9893

3. Address: 1700 BROADWAY SUITE 650

Fax: (866) 522-1673

City: DENVER State: CO Zip: 80290

5. API Number 05-123-35432-00

6. County: WELD

7. Well Name: H-Y

Well Number: 29-51

8. Location: QtrQtr: NENW Section: 29 Township: 6N Range: 67W Meridian: 6

Footage at surface: Distance: 814 feet Direction: FNL Distance: 1943 feet Direction: FWL

As Drilled Latitude: 40.462892 As Drilled Longitude: -104.919474

GPS Data:

Data of Measurement: 07/25/2012 PDOP Reading: 1.7 GPS Instrument Operator's Name: Deb Schwartz

** If directional footage at Top of Prod. Zone Dist.: 1390 feet. Direction: FNL Dist.: 1300 feet. Direction: FEL

Sec: 29 Twp: 6N Rng: 67W

** If directional footage at Bottom Hole Dist.: 1390 feet. Direction: FNL Dist.: 1300 feet. Direction: FEL

Sec: 29 Twp: 6N Rng: 67W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/17/2012 13. Date TD: 07/20/2012 14. Date Casing Set or D&A: 07/21/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7721 TVD** 7317 17 Plug Back Total Depth MD 7665 TVD** 7261

18. Elevations GR 4783 KB 4797

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Triple Combo
Cement Bond
Induction

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	901	670	0	901	
1ST	7+7/8	4+1/2	11.6	0	7,677	609	2,000	7,677	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREELEY SAND	2,261		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,634		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,412		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,945		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,216		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,514		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,536		<input type="checkbox"/>	<input type="checkbox"/>	
GREENHORN	7,588		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Shannon Hartnett

Title: Reg Compl Spec

Date: 11/5/2012

Email: shartnett@gwogco.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400337695	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400337694	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400337687	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400337693	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400353103	PDF-INDUCTION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400353106	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400458802	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400458807	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Back to draft at Opr request.	11/30/2012 3:54:12 PM

Total: 1 comment(s)