

COPPERHEAD LDIS-04
T9N-R58W
SECTION: 15 NWNW

Map Unit Description

Weld County, Colorado, Northern Part

36 Manzanola clay loam, 0 to 3 percent slopes

Setting

Elevation: 4400 to 5600 feet
Mean annual precipitation: 11 to 15 inches
Mean annual air temperature: 46 to 52 degrees F
Frost-free period: 140 to 180 days

Composition

Manzanola and similar soils: 85 percent
Minor components: 15 percent

Description of Manzanola

Setting

Landform: Stream terraces, swales, plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous clayey alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 5 percent
Gypsum maximum: 3 percent
Sodium adsorption ratio maximum: 15.0
Available water capacity: High (about 9.6 inches)

Interpretive Groups

Land capability (non irrigated): 4e
Ecological site: Clayey Plains (R067BY042CO)

Typical Profile

0 to 3 inches: clay loam
3 to 25 inches: clay
25 to 48 inches: clay
48 to 60 inches: clay loam

Minor Components

Avar

Percent of map unit: 15 percent

Map Unit Description

Weld County, Colorado, Northern Part

44 Olney fine sandy loam, 0 to 6 percent slopes

Setting

Elevation: 3500 to 5800 feet
Mean annual precipitation: 11 to 15 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 125 to 175 days

Composition

Olney and similar soils: 85 percent
Minor components: 15 percent

Description of Olney

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous loamy alluvium

Properties and Qualities

Slope: 0 to 6 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.57 to 2.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 8.1 inches)

Interpretive Groups

Land capability (non irrigated): 4c
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 6 inches: fine sandy loam
6 to 18 inches: sandy clay loam
18 to 60 inches: sandy loam
60 to 64 inches: sandy loam

Minor Components

Stoneham

Percent of map unit: 9 percent

Ascalon

Percent of map unit: 6 percent