

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400337879

Date Received:

11/05/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10110

4. Contact Name: Shannon Hartnett

2. Name of Operator: GREAT WESTERN OPERATING COMPANY LLC

Phone: (303) 830-9893

3. Address: 1700 BROADWAY SUITE 650

Fax: (866) 522-1673

City: DENVER State: CO Zip: 80290

5. API Number 05-123-35703-00

6. County: WELD

7. Well Name: Great Western

Well Number: 25-24-23

8. Location: QtrQtr: NWSW Section: 25 Township: 6N Range: 67W Meridian: 6

Footage at surface: Distance: 2357 feet Direction: FSL Distance: 1056 feet Direction: FWL

As Drilled Latitude: 40.457170 As Drilled Longitude: -104.848000

GPS Data:

Data of Measurement: 10/19/2012 PDOP Reading: 1.4 GPS Instrument Operator's Name: D. Schwartz

** If directional footage at Top of Prod. Zone Dist.: 9 feet. Direction: FNL Dist.: 2644 feet. Direction: FWL

Sec: 36 Twp: 6N Rng: 67W

** If directional footage at Bottom Hole Dist.: 9 feet. Direction: FNL Dist.: 2644 feet. Direction: FWL

Sec: 36 Twp: 6N Rng: 67W

9. Field Name: LAPOUDRE SOUTH

10. Field Number: 48130

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 08/04/2012 13. Date TD: 08/13/2012 14. Date Casing Set or D&A: 08/14/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7918 TVD** 7200 17 Plug Back Total Depth MD 7902 TVD** 7184

18. Elevations GR 4751 KB 4765

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Triple Combo
Cement Bond
Induction

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	731	520	0	731	
1ST	7+7/8	4+1/2	11.6	0	7,902	610	2,000	7,914	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREELEY SAND	2,564		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,840		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,591		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,102		<input type="checkbox"/>	<input type="checkbox"/>	
TEEPEE BUTTES	6,592		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,454		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,750		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,772		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Shannon Hartnett

Title: Reg Compl Spec

Date: 11/5/2012

Email: shartnett@gwogco.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400337896	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400337893	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400337879	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400337890	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400353127	PDF-INDUCTION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400353128	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400459168	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400459175	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400459182	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Back to draft at Opr request.	11/30/2012 4:01:24 PM

Total: 1 comment(s)