

**FORM 5**

Rev 02/08

**State of Colorado  
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400421399

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 8960 4. Contact Name: Olga Chikaloff  
 2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY Phone: (720) 440-1600  
 3. Address: 410 17TH STREET SUITE #1400 Fax: (720) 279-2331  
 City: DENVER State: CO Zip: 80202

5. API Number 05-123-36583-00 6. County: WELD  
 7. Well Name: Pronghorn Well Number: K-O-10HNC  
 8. Location: QtrQtr: NWNW Section: 10 Township: 5N Range: 61W Meridian: 6  
 Footage at surface: Distance: 349 feet Direction: FNL Distance: 1272 feet Direction: FWL  
 As Drilled Latitude: 40.422070 As Drilled Longitude: -104.200070

GPS Data:

Date of Measurement: 06/19/2013 PDOP Reading: 1.5 GPS Instrument Operator's Name: Wyatt Hall

\*\* If directional footage at Top of Prod. Zone Dist.: 646 feet. Direction: FNL Dist.: 2629 feet. Direction: FEL

Sec: 10 Twp: 5N Rng: 61w

\*\* If directional footage at Bottom Hole Dist.: 475 feet. Direction: FSL Dist.: 2641 feet. Direction: FWL

Sec: 10 Twp: 5N Rng: 61W

9. Field Name: WILDCAT 10. Field Number: 99999

11. Federal, Indian or State Lease Number: \_\_\_\_\_

12. Spud Date: (when the 1st bit hit the dirt) 04/28/2013 13. Date TD: 05/07/2013 14. Date Casing Set or D&A: 05/11/2013

15. Well Classification:

Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 11084 TVD\*\* 6237 17 Plug Back Total Depth MD 11084 TVD\*\* 6237

18. Elevations GR 4713 KB 4728

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, MUd

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	459	380	0	468	CALC
1ST	8+3/4	7	26	0	6,763	729	0	6,763	VISU
1ST LINER	6+1/8	4+1/2	11.6	6587	11,077				

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,154		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,300		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Olga Chikaloff

Title: Engineering Technician Date: \_\_\_\_\_ Email: ochikaloff@bonanzack.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?	
<b><u>Attachment Checklist</u></b>			
400421410	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400459995	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b><u>Other Attachments</u></b>			
400421408	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400428398	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400459994	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400459998	LAS-	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400460001	PDF-	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)