

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400446743

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Erin Hochstetler Phone: (720)876-5827 Fax: ()

Email: erin.hochstetler@encana.com

7. Well Name: Edith Ann-Duckworth Well Number: 4H-21H O268

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 17347

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 21 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.117610 Longitude: -105.003420

Footage at Surface: 264 feet FNL/FSL FSL 1296 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4927 13. County: WELD

14. GPS Data:

Date of Measurement: 06/06/2013 PDOP Reading: 1.7 Instrument Operator's Name: JOHN RICE

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 898 FSL 158 FWL 460 Bottom Hole: FNL/FSL 100 FEL/FWL FEL
Sec: 22 Twp: 2N Rng: 68W Sec: 21 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 250 ft

18. Distance to nearest property line: 264 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 56 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		640	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T2N-R68W Sec 16: N2NE. Horizontal Wellbore crosses lease lines within drilling and spacing unit; distance to lease line is 0'; distance to unit boundary is at least 460'.
 25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.
 28. Will salt sections be encountered during drilling? Yes No
 29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No
 30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No
 31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**
 Method: Land Farming Land Spreading Disposal Facility Other: _____
 Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	800	100	800	0
1ST	8+3/4	7	26	0	8,046	457	8,046	500
2ND	6+1/8	4+1/2	13.5	0	17,346	364	17,346	7,746

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None
 33. Comments Encana requests the approval of a 318A.a.(1) and 318A.c(1) exception location as the well head is to be located outside of a GWA drilling window and further than 50' from an existing well. Request letter and waivers attached. This well is closer than 150' to the nearest permitted or producing BHL. A 318A.m. variance request letter and waivers are attached. Encana requests the approval of the omission of open hole logs; request letter attached. Proposed spacing unit is T2N-R68W Sec 15: W2W2 Sec 16: E2E2 Sec 21: E2E2 Sec 22: W2W2. The distance to nearest well permitted/completed in the same formation (BHL) is the Jillson 0-6-22, API # 05-123-32564.

34. Location ID: _____
 35. Is this application in a Comprehensive Drilling Plan ? Yes No
 36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No
 I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.
 Signed: _____ Print Name: Erin Hochstetler
 Title: Permitting Technician Date: _____ Email: erin.hochstetler@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ **Director of COGCC** Date: _____

API NUMBER Permit Number: _____ Expiration Date: _____
 05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_MTC' located at: W:\natpub\Nat\Reports\policy_ntc_rdl. Please check th

Attachment Check List

Att Doc Num	Name
400447236	WELL LOCATION PLAT
400447238	DEVIATED DRILLING PLAN
400447239	DIRECTIONAL DATA
400454762	OFFSET WELL EVALUATION
400454763	30 DAY NOTICE LETTER
400454767	OTHER
400454769	PROPOSED SPACING UNIT
400454775	EXCEPTION LOC REQUEST
400454776	EXCEPTION LOC REQUEST
400454778	EXCEPTION LOC WAIVERS

Total Attach: 10 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
Drilling/Completion Operations	Encana will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012.

Total: 2 comment(s)