



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

201015

Date 10-11-12	Well Owner GREAT WESTERN	Well No. 26-14	Lease ANDREWS
County WELD	State COLORADO	Field	
Charge to CADE DRILLING LLC			Charge Code
Address 3450 W. 12 27 #2 (CADE #25)			For Office Use Only
City, State FORT LUTON, COLORADO 80621			
Pump Truck No. 1202	Code	Bulk Truck No. 1214	Code
Type of Job	Depth	Ft. 737	To
Surface 5 3/8" CSG - 24"	Bottom of Surface	Ft. 727	To
Plug	Plug Landed @ 685	Ft. Time On 1930	
Production	Pipe Landed @ 727	Ft. Time Off PLUG DOWN 2145	

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	520	SKS		
	Poz. Mix				
	Calcium Chloride	3%			
	Gel % Flo-Cele 1/4 # Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	5 3/8" CENTRALIZERS	3			
	" CEMENT BASKET	1			
	" GUIDE SHOE	1			
	" BAFFLE PLATE	1			
	BOX THREADLOCK	1			
	MIX RATE 4 BPM	SLURRY VOL 1.18	FT ³ /SK	WATER TEMP 55 OF	
	DISP RATE 5 BPM	SLURRY WT 15.2	PPG		
	PLUG LANDED @ 500 PSI	TOTAL SLURRY VOL 109.2	BBL CEMENT		
Remarks:	PREFLUSH W/20 BBL H2O	Tax Reference Code	Sub Total		
	DISPLACE W/43.5 BBL H2O	State CO 2.9 %	Tax		
	CIRCULATE 5 BBL CEMENT	Disc.	Total		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		24			
1214		Bulk Truck		24			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH Z, ERNIE, TUCKER**

Received By

Customer or His Agent