



02055816

**Well Name:** WPX Energy RMT.  
**Well Name:** RGU 22-27-198  
**Pad Name:** RGU 22-27-198  
**Legal Description:** SENWSEC27TWP1SRNG98W  
**Unit:** Ryan Gulch  
**Unit #** COC070700X  
**COGCC #** 96850  
**API #** 05-103-11959-00  
**County:** Rio Blanco  
**Field:** Sulphur Creek  
**Field #** 80090  
**Rig Name and Number:** CYCLONE 29  
**Williams Supervisor:** Ted Ragsdale  
**Phone number at rig:** 970-988-3854

**RECEIVED**

AUG 06 2013

**COGCC**

This notice, sent on	8/6/2013	is to inform you that Williams
ran and cemented	9-5/8" SURFACE	casing.
Depth casing landed	3,762'	
Volume pumped	193.87, 64.58, 279.26	
Sack of cement used	615, 185, 800	
Cement density	12.8, 12.8, 12.8	
Yield cubic ft/sack	1.77, 1.96, 1.96	
Stages	2 STAGE	
Lift Pressure	890,610	psi
Bumped plug	YES / YES	
Bump pressure	1200, 2300	psi
Floats held	YES / YES	
Returns	FULL / FULL	
Losses	0 / 0	

Additionally:

FULL RETURNS ON BOTH STAGES , / 1STAGE 890 PSI LIFT ,  
BUMPED PLUG , FLOATS HELD, 50 BBLS CEMENT BACK T/  
SURFACE , 2ND STAGE 610 PSI LIFT ,BUMPED CLOSING  
PLUG & TOOL CLOSED , 35 BBLS CEMENT BACK T/ SURFACE  
,CEMENT FELL 35' / WILL TOP OUT ON NEXT SURFACE  
CEMENT JOB/ BLM PRESENT & WITNESSED CEMENT T/  
SURFACE