




02518529

FORM
4
Rev 12/05

Page 2

TECHNICAL INFORMATION PAGE



1. OGCC Operator Number:	10422	API Number:	05-017-06098-00
2. Name of Operator:	Pronghorn Operating LLC	OGCC Facility ID #	
3. Well/Facility Name:	State of Colorado	Well/Facility Number:	2
4. Location (QtrQtr, Sec, Twp, Rng, Meridian):	SWSW, 16, 13S, 44W, 6th		

This form is to be completed whenever a Sundry Notice is submitted requiring detailed report of work to be performed or completed. This form shall be transmitted within 30 days of work completed as a "subsequent" report and must accompany Form 4, page 1.

5.

DESCRIBE PROPOSED OR COMPLETED OPERATIONS**Proposed Re-Entry Operations Plan**

1. Excavate existing 8 5/8" casing stub, weld on extension with 8 5/8" flange. Excavate and level location, dig drilling pit
2. MIRU Drilling Rig
3. MU 7-7/8" bit and drilling assembly
4. Drill out abandonment cement plugs to TD of 5522'
5. Run 5 1/2" casing from surface to approximately 5500' with port collar at sufficient depth to cement upper stage
6. Cement in place with 150 sx 1.42 yield Class A OWC
7. RDMO Drilling Rig
8. Log cement bond log, perforate and test the Mississippian formation
9. Pending results hook up as a commercial well or with abandonment operations per the approved permit