

WELLBORE SCHEMATIC- AS OF 8/1/13

Trilogy Resources, LLC.

Well Name: Wind 17-12

Location: SENW SEC 17, T4N, R67W

API: 05-123-36522

GL Elev: 4794'

KB Elev: 4808'

Spud Date: 4/11/13

Surface Casing

Date: 4/11/2013

8-5/8" 24#

jnts set @ 689'

Cement w/ 450 sx

Top of Cement: Surface- 0'

Top of Cement @ 2450'

Tubing detail- 2 3/8"

5/14/13-Frac'd Codell w/ 4061
 bbls /115,880# of 30/50 sand
 ATR: 60.7 BPM
 MTP: 4492
 Perfs: 7254'-7274' (80 holes)

Production Casing

Date: 4/15/13

4-1/2" 11.6 #

jnts set @ 7454'

Cement w/ 495 sx

PBTD: 7370' TVD: 7256'

TD: 7466' TVD: 7352'

