

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400461341

Date Received:

07/31/2013

PluggingBond SuretyID

20090043

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: SYNERGY RESOURCES CORPORATION 4. COGCC Operator Number: 10311

5. Address: 20203 HIGHWAY 60

City: PLATTEVILLE State: CO Zip: 80651

6. Contact Name: Brianne Visconti Phone: (970)737-1073 Fax: (970)737-1045

Email: bvisconti@syrginfo.com

7. Well Name: Gilbert Well Number: 22-14-11CHZE

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 14891

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 14 Twp: 5N Rng: 66W Meridian: 6

Latitude: 40.399025 Longitude: -104.743180

Footage at Surface: 2482 feet FNL/FSL 2290 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4835 13. County: WELD

14. GPS Data:

Date of Measurement: 07/16/2013 PDOP Reading: 1.0 Instrument Operator's Name: Aaron Demo

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2538 FNL 2540 FWL 480 FNL 2572 FWL 480  
Bottom Hole: FNL/FSL 2540 FNL 2572 FWL 480  
Sec: 14 Twp: 5N Rng: 66W Sec: 11 Twp: 5N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☒ Yes ☐ No

17. Distance to the nearest building, public road, above ground utility or railroad: 335 ft

18. Distance to nearest property line: 163 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1160 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Part of the NWSE/4 of Section 14, 5N, 66W and other lands, lease hold map is attached - Wellbore crosses lease lines within drilling and spacing unit; distance to nearest lease line is 0 feet; distance to Unit boundary is greater than 460'.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 11

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1200	660	1200	0
1ST	8+3/4	7	26	0	6853	125	6853	
1ST LINER	6+1/8	4+1/2	13.5	7978	14891			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments o Conductor casing will not be used. o Operator request an exception location per rule 318 A.a. Request letter and waiver are attached. o Operator requests the proposed spacing unit: 320 Acres, NW/4 of Section 14 and the SW/4 of Section 11, 5N, 66W.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Craig Rasmuson

Title: VP Operations Date: 7/31/2013 Email: crasmuson@syrinfo.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

Data retrieval failed for the subreport 'IntPolicy\_NTC' located at: W:\Inetpub\NetReports\policy\_ntc.rdl. Please check th

## **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
400461341	FORM 2 SUBMITTED
400461365	DIRECTIONAL DATA
400461368	WELL LOCATION PLAT
400461370	PROPOSED SPACING UNIT
400461373	DEVIATED DRILLING PLAN
400461376	OFFSET WELL EVALUATION
400461377	EXCEPTION LOC REQUEST
400461379	EXCEPTION LOC WAIVERS
400462301	LEASE MAP
400463034	LEASE MAP
400464961	SURFACE AGRMT/SURETY

Total Attach: 11 Files

## **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Returned to draft: Permit must have one lease that is within the proposed spacing unit. Leasehold map is nt attached.	8/1/2013 12:11:20 PM

Total: 1 comment(s)

## **Best Management Practices**

<b><u>No</u></b>	<b><u>BMP/COA Type</u></b>	<b><u>Description</u></b>
1	Drilling/Completion Operations	Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
2	Drilling/Completion Operations	Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.

Total: 2 comment(s)