

US ROCKIES REGION

**Anadarko Daily Summary Report**

Well: CANNON LAND 5-3

Project: COLORADO-WELD-NAD83-UTM13	Site: CANNON LAND 5-3	Rig Name No: ENSIGN 328/328
Event: CONST- CAP WELL WORK	Start Date: 7/25/2013	End Date:
Active Datum: RKB @4,971.99usft (above Mean Sea Level)		UWI: 0/2/N/66/W/3/0/NWSW/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	07/25/2013		MIRU Ensign 328, RU Slickline fish tools & tag sand @ 7935, Blow down well & kill it W/ 40 bbls, ND WH NU BOP's, RU PRS EMI out 252 jts 2 3/8 found 11 bad, SWI SDFN.
2	07/26/2013		Crew to loc, PU RBP TIH W/ 97 stands set RBP @ 6006 ND BOP's NU WH roll gas out RU Hydrotester test csg to 5000 psi good test, ND WH NU BOP's TOOH, ND BOP's unland 4 1/2 csg NU dual entry equipment NU BOP's tally in 26 jts 1 1/4 SWI SDFN.
3	07/29/2013		Crew to loc, tih with 76 jts @ 3,313', cir wellbore, miru Sanjel, pump 10 fresh, 20 sms, 5 fresh, 791 SCKS 15.8, class g neat, .25 cello flake, got cmt back to pit, displace 1.5, unable to recover tbg, backe off tbg, ld 7 jts 1.66, nd BOP, nd duel entry,
4	07/30/2013		Crew to loc, miru J-W WIRELINE, run cbl from 3,600' to surface, cement from 3,400' to surface, tih, r head, cir sand cap off rbp, latch on to plug, release plug, tooh, ld rbp, tih, xn profile nipple, nc, land well with 252 jts @ 7,827' kb, broach tbg,