

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HOECHER #1

Project: COLORADO-WELD-NAD83-UTM13

Site: HOECHER #1

Rig Name No: LEED 724/724

Event: CONST- CAP WELL WORK

Start Date: 4/30/2013

End Date:

Spud Date: 3/8/1993

Active Datum: RKB @4,681.99usft (above Mean Sea Level)

UWI: 0/5/N/65/W/35/0/NENE/6/0/0/0/0/0/0

Report No	Report Date	MD (usft)	24 Hr Summary
1	04/30/2013		MIRU Leed 724, TP:200, CP:200, SCP:0. RU pump & tank blew down well & controlled it ND WH NU BOP RU work floor, MI RU Hole Seekers EMI Unit, TOO H tally out 144 good jts LD 75 bad jts. RDMO EMI SWI SDFN.
2	05/01/2013		CT to loc. CP:50 SCP:0, Blew down csg & controlled it MIRU Pioneer Wireline Run Gauge & junk basket to 6775' RIH w/CIBP & set it @ 6730' RDMO wireline, TIH open end tbg down to 6650' MIRU Sanjel cementers pump 50 sxs of cement. SEE REMARKS.
3	05/02/2013		CT to loc. TP:0, CP:0, SCP:0. TIH tbg tagged cement @ 5462' w/173 jts, LD 23 jts. TIH 10 stands from derrick, Land tbg @ 5378' KB. w/170 jts & SN. ND BOP NU WH. SWI. RD Leed 724. Got ready to move.