



**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

## FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 39419

LOCATION Oakley KS

FOREMAN Walt Drake

Colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4-28-13	9160	Pocket Money #1	36	105	56W	Lincoln
CUSTOMER Wiepking Fullerton						
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon Miller		
CITY			5-28-T127	Jerome	Stearns	
STATE						
ZIP CODE						

JOB TYPE	Surface	HOLE SIZE	12 1/4	HOLE DEPTH	105'	CASING SIZE & WEIGHT	
CASING DEPTH	300'	DRILL PIPE		TUBING		OTHER	
SLURRY WEIGHT	15.2	SLURRY VOL		WATER gal/sk		CEMENT LEFT in CASING	20'-30'
DISPLACEMENT	17 1/4	DISPLACEMENT PSI		MIX PSI		RATE	5 BPM

REMARKS: Safety meeting, Rig up equipment on School Bldg, circ. on Bottom, mix 165 SKS Com, 3%CC-2%CC, Release Plug & Displace 17 1/4 H<sub>2</sub>O, Shut in

Carnot Did Curc

Approx 5 BBL to P.H.

Thank You  
Walter Crew

[illegible]


Ravin 3737

AUTHORIZTION Command

**TITLE**

DATE \_\_\_\_\_

**I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.**



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

258936

TICKET NUMBER 39982  
LOCATION Oriskany  
FOREMAN Fuzzy  
miles 5

# FIELD TICKET & TREATMENT REPORT

## CEMENT

color

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-19-13	9160	Pocket Money #1	36	10	56W	Lincoln
CUSTOMER Wayne King Fullerton			Huso 1-500H			
MAILING ADDRESS			0109			
CITY			6W			
STATE			WIA			
ZIP CODE						
TRUCK #	DRIVER	TRUCK #	DRIVER			
156	Jerry Y					
529	Tom W					

JOB TYPE Production HOLE SIZE 7718 HOLE DEPTH 8296' CASING SIZE & WEIGHT 5 1/2 17#  
CASING DEPTH 8293' DRILL PIPE  TUBING  OTHER P-collar - 4892  
SLURRY WEIGHT 14.2 SLURRY VOL 1.24 WATER gal/sk  CEMENT LEFT in CASING 2762  
DISPLACEMENT 191.7 DISPLACEMENT PSI  MIX PSI  RATE

REMARKS: Safety meeting on Monday #25. 3 float, pump Turbolizers #2-3-4-5  
9-12-15-18-20-21-22-23. Cont #81-83- Bask #2-82 (cont) P-collar #82  
Circ 100 JTS in for 2 hrs, run 99 JTS. 300 Cor 1 hr. Pump 500 gal water  
500 gal mud flush, 500 gal water. Mix 10 SKS each #1 & #4. Mix  
330 SKS class 'H' 1090 salt, 290 gal #5. 20 gal / SK. 1 1/4" flo seal. Wash  
pump and lines. Drop plug and displace 192 BSKS. 1500' lift  
Land plug @ 2000' Float held

Thank Fuzzy & Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4550.00	4550.00
5406	100	MILEAGE	5.25	525.00
5407A	16.520	Tow mileage delivery	1.75	2887.50
1115A	350 SKS	Class 'H'	20.27	7094.50
1111	1674*	Salt	1.50	837.00
1110A	1750*	Kal Seal	1.56	980.00
1107	88*	Flo Seal	2.92	261.36
1118B	658*	Benomite	1.28	177.66
1144G	500 gal	mud flush	1.00	500.00
4159	1	5 1/2 - AFU Float shoe	433.25	433.25
4454	1	5 1/2 - Hatchdown Assy	318.25	318.25
4285	1	5 1/2 - Pont collar	2178.25	2178.25
4136	12	5 1/2 - Turbolizers	75.75	909.00
4130	2	5 1/2 - Centralizers	61.00	122.00
4104	2	5 1/2 - Baskets (w)	290.00	580.00
		Subtotal		22354.77
		less 1090		2235.48
		Subtotal		20119.29
		SALES TAX		1010.34
		ESTIMATED TOTAL		21129.63

Ravin 3737

AUTHORIZATION Benny Smith

TITLE Co Rep

DATE 5/19/13

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form



## CEMENT

TICKET NUMBER 39965  
LOCATION Oakley US  
FOREMAN Mike Shaw

REMARKS: Safety Meetings and rigup on Codel Well Service test tool to 1200psi. down tool track injection rate  $3\frac{1}{2}$  bbl/min @ 780 psi min 250 SPS 60/40 per Colgel 28 Calcium Chloride 1/4" Plowel displaced 27 1/2 bbls water Shut tool test to 1200psi. Run in 6 joints 100psi/segment clean. Run tubing to bottom Circulate casing

TSIP 800

SALES TAX	344.30
ESTIMATED TOTAL	8531.25

Ravin 3737

## AUTHORIZTION

**TITLE**

DATE 5-22-2013

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form