

WELLBORE SCHEMATIC- AS OF 8/1/13

Trilogy Resources, LLC.

Well Name: Wind 17-14

Location: SESW SEC 17, T4N, R67W

API: 05-123-36466

GL Elev: 4839'

KB Elev: 4853'

Spud Date: 5/12/13

Surface Casing

Date: 5/12/2013

8-5/8" 24#

jnts set @ 698'

Cement w/ 450 sx

Top of Cement: Surface- 0'

Top of Cement @ 2220'

Tubing detail- 2 3/8"

6/1/13-Frac'd Codell w/ 4268 bbls
/116,080# of 30/50 sand
ATR: 62.0 BPM
MTP: 5975
Perfs: 7370'-7390' (80 holes)

Production Casing

Date: 5/16/13

4-1/2" 11.6 #

jnts set @ 7516'

Cement w/ 571 sx

PBTD: 7502' TVD: 7326'

TD: 7529' TVD: 7353'

