

WELLBORE SCHEMATIC- AS OF 8/1/13

Trilogy Resources, LLC.

Well Name: Wind 17-23

Location: SESW SEC 17, T4N, R67W

API: 05-123-36437

GL Elev: 4841'

KB Elev: 4855'

Spud Date: 4/29/13

Surface Casing

Date: 4/29/2013

8-5/8" 24#

jnts set @ 689'

Cement w/ 450 sx

Top of Cement: Surface- 0'

Top of Cement @ 2700'

Tubing detail- 2 3/8"

5/24/13-Frac'd Codell w/ 4166  
 bbls /115,540# of 30/50 sand  
 ATR: 57.8 BPM  
 MTP: 4703  
 Perfs: 7400'-7420' (80 holes)

Production Casing

Date: 5/4/13

4-1/2" 11.6 #

jnts set @ 7530'

Cement w/ 510 sx

PBTD: 7530' TVD: 7321'

TD: 7563' TVD: 7354'

