

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400445421

Date Received:

07/10/2013

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: Kathleen Mills

2. Name of Operator: NOBLE ENERGY INC

Phone: (720) 587-2226

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 228-4286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-35677-00

6. County: WELD

7. Well Name: THISTLE DOWN STATE PC

Well Number: F36-65HN

8. Location: QtrQtr: SENE Section: 36 Township: 5N Range: 65W Meridian: 6

Footage at surface: Distance: 2337 feet Direction: FNL Distance: 279 feet Direction: FEL

As Drilled Latitude: 40.356450 As Drilled Longitude: -104.603050

GPS Data:

Date of Measurement: 04/12/2013 PDOP Reading: 2.7 GPS Instrument Operator's Name: BRANDI BINGHAM

** If directional footage at Top of Prod. Zone Dist.: 2463 feet. Direction: FNL Dist.: 861 feet. Direction: FEL

Sec: 36 Twp: 5N Rng: 65W

** If directional footage at Bottom Hole Dist.: 2450 feet. Direction: FNL Dist.: 629 feet. Direction: FWL

Sec: 36 Twp: 5N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number: 81/6053-S

12. Spud Date: (when the 1st bit hit the dirt) 01/28/2013 13. Date TD: 02/07/2013 14. Date Casing Set or D&A: 02/08/2013

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11142 TVD** 6911 17 Plug Back Total Depth MD 11126 TVD** 6910

18. Elevations GR 4770 KB 4788

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, MUD, GR

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	20	42.09	0	98	80	0	98	VISU
SURF	13+3/4	9+5/8	36	0	626	395	0	626	VISU
1ST	8+3/4	7	26	0	7,262	659	1,200	7,262	CBL
1ST LINER	6+1/8	4+1/2	1.6	7109	11,127				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,499		<input type="checkbox"/>	<input type="checkbox"/>	
PARKMAN	3,931		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,444		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,194		<input type="checkbox"/>	<input type="checkbox"/>	
TEEPEE BUTTES	6,267		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,046		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kathleen Mills

Title: Regulatory Analyst Date: 7/10/2013 Email: kmills@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400445443	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400445445	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400445421	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445427	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445432	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445433	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445434	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445436	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445437	LAS-GAMMA RAY	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400445446	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)