

## Bledsoe 13X-2-5-45 P&A'd

**Location:** T5N, R45W, Sec 2

**County:** Yuma

**Spud Date:** 6/24/2013

**TD Date:** 6/26/2013

**API:** 05-125-11969

Cmt surface casing w/ 230 sxs of  
50/50 POZ, 3% CaCl, 1.07 yield,  
15.2# density.

3rd plug set @ surface w/ 10 sxs

9 7/8" hole

7" surface casing, 17# J-55 @ 478'

2nd plug set @ 565'-345' half in, half out  
w/ 35 sxs

6 1/4" open hole

1st plug set @  
2512-2292' w/  
35 sxs

TD: 2736'