

06/27/13 - (MAZ) @ 7:00 AM @ TD of 2736' & Cmnt 1st plug. (818') - Previous 24 Hrs – Mud wt.___, Vis ___; Drl 6-1/4" hole; Dev surv 1/2° @ 1941'; Drl 6-1/4" hole; Dev surv 1° @ 2202'; Drl 6-1/4" hole; Dev surv 3/4° @ 2297'; Drl 6-1/4" hole; Dev surv 2° @ 2518'; Drl 6-1/4" hole to TD of 2736' @ 4:45 PM, 06/26/13; Cond mud & circ; TIH; Circ; Dev surv 1-1/4° @ 2736'; TOOH; LDDC; Log well; TIH to P&A; Circ; TOOH; LDDC; LDDP; Safety mtg w/Bison; 1st plug set @ 2512 - 2292' w/(35) sxs.

06/28/13 - (MAZ) @ 7:00 AM @ TD of 2736' & RDMO. (0') - Previous 24 Hrs – Mud wt.___, Vis ___; 2nd plug set @ 565' – 345', half in, half out w/(35) sxs, 3rd plug set @ surf w/(10) sxs – total of (80) bags of 50/50 POZ, 2% Gel, yield 1.35, 13.8# density; PB @ 8:15 AM, 06/27/13; Clean tanks; Rig Release @ 8:45 AM, 06/27/13; RDMO.