

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400470830

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322  
2. Name of Operator: NOBLE ENERGY INC  
3. Address: 1625 BROADWAY STE 2200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Eileen Roberts  
Phone: (303) 2284330  
Fax: (303) 2284286

5. API Number 05-123-35596-00  
6. County: WELD  
7. Well Name: ROACH  
Well Number: N14-65-1HN  
8. Location: QtrQtr: NESE Section: 14 Township: 5N Range: 67W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 07/10/2013 End Date: 07/10/2013 Date of First Production this formation: 07/20/2013

Perforations Top: 7555 Bottom: 11255 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Nibrara w/ 2888129 gals of Silverstim and Slick Water with 3004340#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 68764 Max pressure during treatment (psi): 7455

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.92

Total acid used in treatment (bbl): 0 Number of staged intervals: 20

Recycled water used in treatment (bbl): 3119 Flowback volume recovered (bbl): 285

Fresh water used in treatment (bbl): 65645 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 3004340 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/24/2013 Hours: 24 Bbl oil: 369 Mcf Gas: 445 Bbl H2O: 211

Calculated 24 hour rate: Bbl oil: 369 Mcf Gas: 445 Bbl H2O: 211 GOR: 1205

Test Method: FLOWING Casing PSI: 2417 Tubing PSI: 1182 Choke Size: 016/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1318 API Gravity Oil: 40

Tubing Size: 2 + 7/8 Tubing Setting Depth: 7310 Tbg setting date: 07/18/2013 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Eileen Roberts \_\_\_\_\_

Title: Regulatory Specialist \_\_\_\_\_

Date: \_\_\_\_\_

Email: eroberts@nobleenergyinc.com \_\_\_\_\_

:

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
---------------------------	--------------------

--	--

Total Attach: 0 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>
--------------------------	-----------------------

<b><u>Comment Date</u></b>
----------------------------

--	--	--

Total: 0 comment(s)